

Our Ref: SDW3676/24

Enquiries: *Rabin Khad Thakuri*
Tel: (03) 8754 4999

20 October 2025

Spiire Australia Pty Ltd
L 6 414 La Trobe St
MELBOURNE VIC 3000

Dear Rafe Wilson

RE: HARLOW STAGE 6 - AMENDMENTS TO CONSTRUCTION PLAN APPROVAL

Please be advised that the amended construction plans submitted to Council for Harlow Stage 6 are approved.

- **Road Name Amended.**

A copy of the following approved plans have been enclosed for your information.

- Drawing No. 309442CR100 Revision 3
- Drawing No. 309442CR200 Revision 3
- Drawing No. 309442CR202 Revision 3
- Drawing No. 309442CR203 Revision 3
- Drawing No. 309442CR300 Revision 3
- Drawing No. 309442CR400 Revision 3
- Drawing No. 309442CR500 Revision 3
- Drawing No. 309442CR700 Revision 3
- Drawing No. 309442CR800 Revision 3

Yours sincerely,



ABUL HOSSEN
SUBDIVISIONS CO-ORDINATOR



Civic Centre
Postal

Telephone
Facsimile
Email

45 Princes Highway, Werribee, Victoria 3030, Australia
PO Box 197, Werribee, Victoria 3030, Australia

(03) 9742 0777
(03) 9741 6237
mail@wyndham.vic.gov.au
www.wyndham.vic.gov.au

DX 30258 Werribee Vic
ABN: 38 393 903 860

Your Ref:

Our Ref: SDW3676/24
WYP13902/22

Enquiries: Rabin Khad Thakuri
Tel: (03) 8754 4999

25 March 2025

Spiire Australia Pty Ltd
L 6 414 La Trobe St
MELBOURNE VIC 3000

Dear Rafe Wilson

RE: HARLOW STAGE 6 - CONSTRUCTION PLAN APPROVAL

Please be advised that the road and drainage construction plans submitted to Council for Harlow Stage 6 are approved subject to the following conditions:-

1. **Prior to the issue of a Statement of Compliance (SOC) for the stage 6, the signalised intersection at Derrimut Road and the east-west connector Road must be constructed to the satisfaction of Responsible Authority and relevant Road Authority**
2. Prior to the placement of concrete kerb and channel, all constructed drainage lines, including easement drains and AG drains, must undergo inspection by an independent testing organisation using closed circuit television (CCTV). Report must be provided to Council as per Wyndham City Council's Technical Specification Section 701 – Underground Stormwater Drains.
3. **Prior to commencement of works, an on-site pre-commencement meeting must be held between Council, the Engineering Consultant and the Contractor. Please contact Robert Troiano from Council on 0407802834 to book a precommencement meeting.**
4. **Prior to installation of any Tactile Ground Surface Indicators, the proposed product must be inspected and approved by Council. Please notify Councils construction supervisor to book an inspection prior to installation.**
5. **Prior to commencement of works, the Plan of Subdivision must be certified by Council.**
6. **Prior to commencement of approved works within ANY existing road reserves, the consultant/contractor MUST apply for consent to work within the road reserves from Council or any other relevant responsible authorities. The Contractor will be responsible for maintain all existing assets within the limit of works as demonstrated on the approved plans.**
7. **A free-flowing drainage outlet must be established and maintained throughout the entirety of construction works. No road boxing works are to commence in the absence of a free-flowing drainage outlet.**
8. Prior to commencement of works, the consultant/contractor shall provide to Council the following information:-

- source of quarry material; and
- optimum moisture content and maximum modified dry density of the F.C.R to be used (from N.A.T.A. approved laboratory).

If the source of the quarry material is changed during the course of the works, new test results shall be provided.

- Please provide a Site Environment Management Plan (SEMP) to Council for approval. To submit a SEMP, complete Wyndham Council's online form after following the instructions on the website.
- Construction is to commence within twelve (12) months of approval, otherwise construction plans and specifications are to comply with design standards current at the time of re-submission.
- Filled allotments shall be compacted in 150mm maximum layers, with compaction tests being taken at not more than 300mm lift on all allotments and filled areas. The test results and location of the tests on each allotment shall be forwarded to Council.
- Wyndham City Council Specifications and standard details shall be read in conjunction with the approved plans.
- Prior to Council issuing a Statement of Compliance, pursuant to the Subdivision Act 1988, your firm shall provide to Council the following:
 - Payment of construction supervision fees amounting to 2.5% of the total cost of road and drainage works;
 - Payment of a maintenance bond amounting to 5% of the total cost of road and drainage works;
 - An electronic copy of all as constructed drawings and relevant files in both AutoCad DWG and Adobe PDF file formats, to either subdiveng@wyndham.vic.gov.au or via Objective Connect. Please note that the minimum resolution of PDF files required is 300dpi;
 - An electronic copy of drainage catchment plans and detailed computations in Adobe PDF file format to either subdiveng@wyndham.vic.gov.au or via Objective Connect;
 - As constructed asset information for drainage and related assets in digital format in accordance with "D-Spec" to either subdiveng@wyndham.vic.gov.au or via Objective Connect; and
 - As-constructed asset information for assets within the road reserve in digital format in accordance with "R-Spec" to either subdiveng@wyndham.vic.gov.au or via Objective Connect; and
 - The A.H.D levels and M.G.A co-ordinates of the high stability P.S.Ms.
 - For further information please see: <https://www.wyndham.vic.gov.au/subdivisionguidelines>
- Easements are to be created to cover all services which cross any part of private allotments.
- During construction of works under this permit, access to and egress from the subject land must be via a route designed and approved by the Council. Where practical this access should be remote from established residential areas.
- Provide Landscaping Plan for approval by Council. Please contact subdivlud@wyndham.vic.gov.au to arrange a pre-application meeting prior to the submission of landscape plans for municipal reserves and/or public open space.
- WorkSafe Victoria is to be advised via E-mail (construction@workcover.vic.gov.au) of these Subdivisional works with the following details:
 - Name of the principal contractor
 - Name and phone contact of relevant Engineering Consultants supervisor dealing with the works
 - Brief description of the works
 - Locality/address of the works
 - Estimated commencement date of the works, and
 - Expected completion date of the works.

18. In undertaking the construction works, the developer shall ensure all works are undertaken in accordance with the OH & S Act, Regulation and Codes, and shall maintain a safe workplace for Council's staff undertaking inspections. The supervision of works by Council staff only extends to the quality of Council's future infrastructure and does not include ensuring that the works are undertaken safely.

Please find a set of stamped approved plans attached.

Yours sincerely,




KABI CHAPAGAIN

TEAM LEADER DEVELOPMENT ENGINEER

Encl: (1) Stamped approved plans

file name: 309442CR200.dwg, layout name: CR200, plotted by: Thanh Nguyen,
file location: G:\309442\309442.dwg, ACAD plot date: 02/10/2025 9:32 AM, Sheet: 2 of 17 Sheets



Planning and Environment Act 1987
Wyndham Planning Scheme

Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 20/10/2025



WARNING
BEWARE OF UNDERGROUND/OVERHEAD SERVICES
THE LOCATION OF SERVICES ARE APPROXIMATE ONLY, AND THEIR
EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS
GIVEN THAT ALL EXISTING SERVICES ARE SHOWN. SPECIAL
CONSIDERATION SHOULD BE GIVEN TO CONSTRUCTION PROCEDURES
UNDER OVERHEAD ELECTRICITY TRANSMISSION LINES.

Rev	Amendments	Approved	Date
2	ROAD NAME AMENDED	G.K	01/10/25
1	INDUSTRIAL CROSSOVER ADDED	G.K	23/07/25
0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
D	LOT NO & SWD ALIGNMENT AMENDED, BATTER ADDED	G.K	28/01/25
C	LOT LAYOUT, LEVELS & NOTES AMENDED; PRAM CROSSING & TGSIS ADDED	G.K	18/12/24
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24



© Spiire Australia Pty Ltd All Rights Reserved
This document is produced by Spiire Australia Pty Ltd solely for the
benefit of and use by the client in accordance with the terms of the
retainer. Spiire Australia Pty Ltd does not and shall not assume any
responsibility or liability whatsoever to any third party arising out of
any use or reliance by third party on the content of this document.




L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635



Designed T. NGUYEN	Checked G. KOHLMAN
Authorised G. KOHLMAN	Date 01/11/24

**HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
FACE PLAN - SHEET 1
WYNDHAM CITY COUNCIL
SIG GROUP**

CONSTRUCTION Drg No **309442CR200** Rev **2**




Planning and Environment Act 1987
Wyndham Planning Scheme

**Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 25/03/2025**



WARNING
BEWARE OF UNDERGROUND/OVERHEAD SERVICES
THE LOCATION OF SERVICES ARE APPROXIMATE ONLY. AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN. SPECIAL CONSIDERATION SHOULD BE GIVEN TO CONSTRUCTION PROCEDURES UNDER OVERHEAD ELECTRICITY TRANSMISSION LINES.

0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24
Rev	Amendments	Approved	Date



© Spiire Australia Pty Ltd All Rights Reserved
This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

spiire

L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635




Designed
T. NGUYEN
Authorised
G. KOHLMAN

Checked
G. KOHLMAN
Date
01/11/24

**HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
FACE PLAN - SHEET 2
WYNDHAM CITY COUNCIL
SIG GROUP**

CONSTRUCTION Drg No Rev
309442CR201 **0**



Planning and Environment Act 1987
Wyndham Planning Scheme

Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 20/10/2025

SERVICE LOCATION TABLE

ROAD NAME	POTABLE WATER		RECYCLED WATER		GAS		NBN (TELECOM)		ELECTRICITY			
	SIDE	OFFSET	SIDE	OFFSET	SIDE	OFFSET	SIDE	OFFSET	POLE SIDE	OFFSET	U/G CABLE SIDE	OFFSET
TURMERIC STREET	S	2.90	S	2.40	S	1.90	N	1.85	N	0.90 x	N	2.60
JIRA CRESCENT (N/S)	W	3.00	W	2.50	W	2.10	E	1.85	E	0.90 x	E	2.60
JIRA CRESCENT (E/W)	S	3.25	S	2.75	S	2.25	S	1.85	N	0.90 x	N	1.00
SPRINGFALL ROAD	N	3.10	N	2.50	N	2.00	S	2.35	S	0.90 x	S	2.95


- TELECOMMUNICATIONS AND ELECTRICITY CABLES TO BE CONSTRUCTED IN A COMMON TRENCH IN ACCORDANCE WITH ELECTRICITY AUTHORITY STANDARD DRG'S.
- GAS AND WATER MAINS TO BE CONSTRUCTED IN A COMMON TRENCH.
- x = OFFSET FROM BACK OF KERB

NOTE: TREE LOCATIONS SHOWN ARE INDICATIVE ONLY. REFER TO LANDSCAPE ARCHITECT PLANS FOR FINAL LOCATIONS

WARNING
BEWARE OF UNDERGROUND/OVERHEAD SERVICES
THE LOCATION OF SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN. SPECIAL CONSIDERATION SHOULD BE GIVEN TO CONSTRUCTION PROCEDURES UNDER OVERHEAD ELECTRICITY TRANSMISSION LINES.

file name: 309442CR202.dwg, layout name: CR202, plotted by: Thanh Nguyen, file location: G:\30309442\309442.dwg, ACAD plot date: 02/10/2025 9:32 AM, Sheet 4 of 17 Sheets

2	ROAD NAME AMENDED	G.K	01/10/25
1	SERVICE CONDUIT ADDED, PIT SIZE & PIT HAUNCHES AMENDED	G.K	23/07/25
0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
D	NOTES, SWD SIZE & SWD ALIGNMENT AMENDED	G.K	28/01/25
C	LOT LAYOUT, SERVICES CONNECTIONS, NOTES, SWD & SEWER AMENDED; TREES & EXISTING TREES ADDED	G.K	18/12/24
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24
Rev	Amendments	Approved	Date



L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 3007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635



Designed
T. NGUYEN

Authorised
G. KOHLMAN


Checked
G. KOHLMAN

Date
01/11/24

**HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
SERVICES PLAN - SHEET 1
WYNDHAM CITY COUNCIL
SIG GROUP**

CONSTRUCTION Drg No 309442CR202 Rev 2

file name: 309442CR203.dwg, layout name: CR203, plot style: Trench Nguyen, file location: G:\30\309442\309442.dwg, plot date: 02/10/2025 9:37 AM, sheet: 5 of 17, sheets



Planning and Environment Act 1987
Wyndham Planning Scheme

Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 20/10/2025

FOR CONTINUATION REFER TO SHEET CR202


3

SERVICE LOCATION TABLE

ROAD NAME	POTABLE WATER		RECYCLED WATER		GAS		NBN (TELECOM)		ELECTRICITY			
	SIDE	OFFSET	SIDE	OFFSET	SIDE	OFFSET	SIDE	OFFSET	POLE	POLE	U/G CABLE	U/G CABLE
TURMERIC STREET	S	2.90	S	2.40	S	1.90	N	1.85	N	0.90 x	N	2.60
JIRA CRESCENT (N/S)	W	3.00	W	2.50	W	2.10	E	1.85	E	0.90 x	E	2.60
JIRA CRESCENT (E/W)	S	3.25	S	2.75	S	2.25	S	1.85	N	0.90 x	N	1.00
SPRINGFALL ROAD	N	3.10	N	2.50	N	2.00	S	2.35	S	0.90 x	S	2.95

1. TELECOMMUNICATIONS AND ELECTRICITY CABLES TO BE CONSTRUCTED IN A COMMON TRENCH IN ACCORDANCE WITH ELECTRICITY AUTHORITY STANDARD DRG's.
2. GAS AND WATER MAINS TO BE CONSTRUCTED IN A COMMON TRENCH.
3. * = OFFSET FROM BACK OF KERB

3	ROAD NAME AMENDED	G.K	01/10/25
2	NOTES AMENDED	G.K	04/08/25
1	PIT SIZE & PIT HAUNCH AMENDED	G.K	23/07/25
0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
D	NOTES AMENDED	G.K	28/01/25
C	NOTES, SEWER ALIGNMENT AND SWD SIZES AMENDED	G.K	18/12/24
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24
Rev	Amendments	Approved	Date




© Spiire Australia Pty Ltd All Rights Reserved
This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

spiire
L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635

Harlow
TARNEIT
Designed
T. NGUYEN
Authorised
G. KOHLMAN
Checked
G. KOHLMAN
Date
01/11/24

**HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
SERVICES PLAN - SHEET 2
WYNDHAM CITY COUNCIL
SIG GROUP**
CONSTRUCTION
Drg No
309442CR203
Rev
3


WARNING
BEWARE OF UNDERGROUND/OVERHEAD SERVICES
THE LOCATION OF SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN. SPECIAL CONSIDERATION SHOULD BE GIVEN TO CONSTRUCTION PROCEDURES UNDER OVERHEAD ELECTRICITY TRANSMISSION LINES.



JIRA CRESCENT


Scale

H 1500
SCALE @ A1
V 150



0 5 10 15 20 25


0 0.5 1 1.5 2 2.5




file name 309442CR300.dwg, layout name CR301, plotted by, Thanh Nguyen,
file location G:\301\309442\309442\CR301\CR301.dwg, plot date 19/03/2025 3:41 PM, Sheet 7 of 17 Sheets

Planning and Environment Act 1987
Wyndham Planning Scheme

Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 25/03/2025



Rev	Amendments	Approved	Date
0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
C	ROAD LONG SECTION AMENDED	G.K	18/12/24
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24



Designed T. NGUYEN	Checked G. KOHLMAN
Authorised G. KOHLMAN	Date 01/11/24

HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
ROAD LONG SECTIONS - SHEET 2
WYNDHAM CITY COUNCIL
SIG GROUP

CONSTRUCTION Drg No **309442CR301** Rev **0**


FILLING NOTE
ALL FILLING WITHIN ROAD RESERVES IS TO BE UNDERTAKEN USING LEVEL 1 SUPERVISION AND BE COMPLETED IN ACCORDANCE WITH AS 3798-2007 AND TO THE SATISFACTION OF COUNCIL AND THE SUPERINTENDENT. FILL AREAS ARE TO BE STRIPPED OF TOPSOIL, FILLED AND REPLACED WITH TOPSOIL (WHERE REQUIRED) TO OBTAIN THE FINAL LEVELS SHOWN ON THE DRAWINGS.

STRUCTURAL FILL IN ACCORDANCE WITH AS3798-2007, LEVEL 1

Planning and Environment Act 1987
Wyndham Planning Scheme


Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 20/10/2025

2




TURMERIC STREET

CH 59.42




TURMERIC STREET

CH 40.22




TURMERIC STREET

CH 13.22




TURMERIC STREET

CH 128.72



TURMERIC STREET

CH 112.72




TURMERIC STREET


CH 83.02

file name: 309442CR400.dwg, layout name: CR400, plotted by: Thanh Nguyen, file location: G:\309442\309442.dwg, VBA CAD plot date: 02/10/2025 03:27 AM, Sheet 8 of 17 Sheets

2	ROAD NAME & BOXING AMENDED	G.K	01/10/25
1	BOXING AMENDED	G.K	23/07/25
0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
C	ROAD CROSS SECTIONS AMENDED	G.K	18/12/24
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24
Rev	Amendments	Approved	Date



Designed T. NGUYEN	Checked G. KOHLMAN
Authorised G. KOHLMAN	Date 01/11/24





HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
ROAD CROSS SECTIONS - SHEET 1
WYNDHAM CITY COUNCIL
SIG GROUP

CONSTRUCTION

Drg No
309442CR400


Rev
2

ALL FILLING WITHIN ROAD RESERVES IS TO BE UNDERTAKEN USING LEVEL 1 SUPERVISION AND BE COMPLETED IN ACCORDANCE WITH AS 3798-2007 AND TO THE SATISFACTION OF COUNCIL AND THE SUPERINTENDENT. FILL AREAS ARE TO BE STRIPPED OF TOPSOIL, FILLED AND REPLACED WITH TOPSOIL (WHERE REQUIRED) TO OBTAIN THE FINAL LEVELS SHOWN ON THE DRAWINGS.

[illegible]


JIRA CRESCENT

CH 1009.21

[illegible]

JIRA CRESCENT



CH 994.01



DATUM R.L.	48.0
DESIGN SURFACE LEVEL	49.544 49.717 49.715
EXISTING SURFACE LEVEL	49.538 49.685
OFFSET	-7.750 -7.700 -6.200 -2.900 -2.300 0.000 2.300 2.900 5.750

JIRA CRESCENT


CH 963.51



DATUM R.L.48.0					
DESIGN SURFACE LEVEL					
	-8.000	49.719	49.823		
	-7.950	49.719	49.822		
EXISTING SURFACE LEVEL					
	-6.450	49.735	49.792		
	-3.800	49.760	49.703		
	-3.200	49.764	49.593		
OFFSET					
	0.000	49.800	49.700		
	3.200	49.816	49.593		
	3.800	49.818	49.703		
	6.450	49.826	49.792		
	7.950	49.831	49.822		
	8.000	49.831	49.823		

JIRA CRESCENT


CH 1084.77



DATUM R.L. 48.0					
DESIGN SURFACE LEVEL			49.84 49.83		
EXISTING SURFACE LEVEL			49.76 49.76	49.86 49.54	
OFFSET	-8.00 -7.95		49.78 49.78	49.98 49.98	

JIRA CRESCENT

CH 1052.57




DATUM R.L.48.0							
DESIGN SURFACE LEVEL							
	-8.000	4.973	50.06				
	-7.950	4.973	50.04				
EXISTING SURFACE LEVEL							
		4.991	50.074				
	-3.800	50.032	4.986				
	-3.200	50.044	4.976				
		50.095	4.983				
	0.000						
	3.200	50.024	4.976				
	3.800	50.032	4.986				
	6.450	50.063	50.074				
	7.950	50.080	50.04				
	8.000	50.081	50.06				

JIRA CRESCENT

CH 1028.22

0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
C	ROAD CROSS SECTIONS AMENDED	G.K	18/12/24
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24
Rev	Amendments	Approved	Date



© Spiire Australia Pty Ltd All Rights Reserved
This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635



Designed	Checked
T. NGUYEN	G. KOHLMAN
Authorised	Date
G. KOHLMAN	01/11/24

**HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
ROAD CROSS SECTIONS - SHEET 2
WYNDHAM CITY COUNCIL
SIG GROUP**

CONSTRUCTION Drg No **309442CR401**


0

FILLING NOTE
ALL FILLING WITHIN ROAD RESERVES IS TO BE UNDERTAKEN USING LEVEL 1 SUPERVISION AND BE COMPLETED IN ACCORDANCE WITH AS 3798-2007 AND TO THE SATISFACTION OF COUNCIL AND THE SUPERINTENDENT. FILL AREAS ARE TO BE STRIPPED OF TOPSOIL, FILLED AND REPLACED WITH TOPSOIL (WHERE REQUIRED) TO OBTAIN THE FINAL LEVELS SHOWN ON THE DRAWINGS.

 STRUCTURAL FILL IN ACCORDANCE WITH AS3798-2007, LEVEL 1


Planning and Environment Act 1987
Wyndham Planning Scheme

Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 25/03/2025




SPRINGFALL ROAD

CH 58.22




SPRINGFALL ROAD

CH 20.22



SPRINGFALL ROAD

CH 112.72




SPRINGFALL ROAD


CH 86.22

file name 309442CR402.dwg, layout name CR402, plotted by: Thanh Nguyen, file location G:\309442\309442\309442\CR402\309442.dwg, plot date: 19/03/2025 3:41 PM, Sheet 10 of 17 Sheets

Rev	Amendments	Approved	Date
0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
D	ROAD CROSS SECTIONS AMENDED	G.K	28/01/25
C	ROAD CROSS SECTIONS AMENDED	G.K	18/12/24
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24



Designed T. NGUYEN	Checked G. KOHLMAN
Authorised G. KOHLMAN	Date 01/11/24



HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
ROAD CROSS SECTIONS - SHEET 3
WYNDHAM CITY COUNCIL
SIG GROUP

CONSTRUCTION

Drg No
309442CR402

Rev
0



FUTURE
CHILDCARE

Planning and Environment Act 1987
Wyndham Planning Scheme
Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 20/10/2025



POINT NO	EASTING	NORTHING	RL
A1	297803.347	5812745.583	49.741
A2	297803.100	5812745.108	49.746
A3	297801.463	5812743.728	49.784
A4	297801.005	5812742.845	49.784
1/4	297801.377	5812739.510	49.746
1/2	297802.996	5812736.571	49.691
3/4	297805.617	5812734.476	49.640
A5	297808.840	5812733.543	49.612
A6	297810.285	5812733.419	49.619

CURVE	RADIUS	ARC L	CHORD	MID ORD	QTR ORD
A1-A2	0.700	0.550	0.536	0.053	0.013
A3-A4	1.300	1.021	0.995	0.099	-0.025
A4-A5	8.600	13.509	12.162	2.519	-0.655



POINT NO	EASTING	NORTHING	RL
B1	297809.740	5812727.043	49.619
B2	297808.295	5812727.166	49.612
1/4	297804.960	5812727.694	49.584
3/2	297802.021	5812725.175	49.556
1/4	297799.926	5812722.554	49.529
B3	297798.993	5812719.331	49.501
B4	297799.294	5812718.382	49.502
B5	297800.674	5812716.744	49.475
B6	297800.836	5812716.234	49.470

CURVE	RADIUS	ARC L	CHORD	MID ORD	QTR ORD
B2-B3	8.600	13.509	12.162	2.519	-0.655
B3-B4	1.300	1.021	0.995	0.099	-0.025
B5-B6	0.700	0.550	0.536	0.053	0.013



POINT NO	EASTING	NORTHING	RL
C1	297856.317	5812729.481	49.518
1/4	297859.652	5812729.853	49.535
1/2	297862.591	5812731.473	49.552
3/4	297864.686	5812734.094	49.573
C2	297865.619	5812737.317	49.593

CURVE	RADIUS	ARC L	CHORD	MID ORD	QTR ORD
C1-C2	8.600	13.509	12.162	2.519	-0.655



POINT NO	EASTING	NORTHING	RL
D1	297871.996	5812736.771	49.593
1/4	297872.367	5812733.437	49.560
1/2	297873.987	5812730.498	49.495
3/4	297876.608	5812728.402	49.428
D2	297879.831	5812727.470	49.390

CURVE	RADIUS	ARC L	CHORD	MID ORD	QTR ORD
D1-D2	8.600	13.509	12.162	2.519	-0.655




POINT NO	EASTING	NORTHING	RL
E1	297870.439	5812793.661	49.876
E2	297870.746	5812797.248	49.895
1/4	297871.787	5812800.846	49.914
1/2	297874.126	5812803.772	49.934
3/4	297877.407	5812805.580	49.953
E3	297881.129	5812805.995	49.973
E4	297886.510	5812805.535	50.001

CURVE	RADIUS	ARC L	CHORD	MID ORD	QTR ORD
E2-E3	9.600	15.080	13.576	2.812	0.731




POINT NO	EASTING	NORTHING	RL
F 1	297886.117	5812800.951	50.000
1/4	297882.783	5812800.580	49.970
1/2	297879.844	5812798.960	49.938
3/4	297877.749	5812796.339	49.907
F2	297876.816	5812793.116	49.876

CURVE	RADIUS	ARC L	CHORD	MID ORD	QTR ORD
F1-F2	8.600	13.509	12.162	2.519	-0.655



KARB RETURN SETOUT DETAIL

1	ROAD NAME AMENDED	G.K	01/10/25
0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24
Rev	Amendments	Approved	Date



© Spiire Australia Pty Ltd All Rights Reserved



L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635



Designed
T. NGUYEN
Authorised
G. KOHLMAN

Checked
G. KOHLMAN
Date
01/11/24


HARLOW ESTATE STAGE 6 ROAD AND DRAINAGE INTERSECTION DETAILS WYNDHAM CITY COUNCIL SIG GROUP

CONSTRUCTION Drg No **309442CR500** Rev **1**

File name 309442CR500.dwg layout name CR500 plotted by Thanh Nguyen
File location G:\30\309442\Civil\ACAD plot date 02/10/2025 9:33 AM Sheet 11 of 17 Sheets



CRUSHED ROCK BACKFILL




Planning and Environment Act 1987
Wyndham Planning Scheme

Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 25/03/2025

file name 309442CR600.dwg, layout name CR600, plotted by Thanh Nguyen,
file location G:\309442\309442\CR600\309442.dwg, PWS sheet 12 of 17 Sheets

Rev	Amendments	Approved	Date
0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
D	DRAINAGE LONG SECTION AMENDED	G.K	28/01/25
C	DRAINAGE LONG SECTIONS AMENDED	G.K	18/12/24
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24



Designed T. NGUYEN	Checked G. KOHLMAN
Authorised G. KOHLMAN	Date 01/11/24

HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
DRAINAGE LONG SECTIONS - SHEET 1
WYNDHAM CITY COUNCIL
SIG GROUP

CONSTRUCTION



Dwg No
309442CR600

Rev
0


file name: 309442CR600.dwg, layout name: CR601, plot date: 19/03/2025 3:41 PM, Sheet 13 of 17, Sheets

Planning and Environment Act 1987
Wyndham Planning Scheme

Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 25/03/2025



Rev	Amendments	Approved	Date
0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
D	DRAINAGE LONG SECTIONS AMENDED	G.K	28/01/25
C	DRAINAGE LONG SECTIONS AMENDED	G.K	18/12/24
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24



Designed T. NGUYEN	Checked G. KOHLMAN
Authorised G. KOHLMAN	Date 01/11/24









**HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
DRAINAGE LONG SECTIONS - SHEET 2
WYNDHAM CITY COUNCIL
SIG GROUP**

CONSTRUCTION

Drg No
309442CR601

Rev
0



file name: 309442CR602.dwg, layout name: CR602, plotted by: Thanh Nguyen,
file location: \\spiremedia\data\309442, plot date: 19/03/2025 3:41 PM, Sheet 14 of 17 Sheets



Planning and Environment Act 1987
Wyndham Planning Scheme

Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 25/03/2025

Rev	Amendments	Approved	Date
0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
D	DRAINAGE LONG SECTIONS AMENDED	G.K	28/01/25
C	DRAINAGE LONG SECTIONS AMENDED	G.K	18/12/24
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24



spiire

L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635

Harlow
T A R N E I T

Designed
T. NGUYEN
Authorised
G. KOHLMAN

Checked
G. KOHLMAN
Date
01/11/24

HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
DRAINAGE LONG SECTIONS - SHEET 3
WYNDHAM CITY COUNCIL
SIG GROUP

CONSTRUCTION
309442CR602

Dwg No

Rev

0

DRAINAGE PIT SCHEDULE

PIT		INTERNAL		INLET		OUTLET		PIT		REMARKS
NAME	TYPE	WIDTH	LENGTH	DIA	INV LEVEL	DIA	INV LEVEL	FS LEVEL	DEPTH	
EX1	JUNCTION PIT	900	900	675	46.680	675	46.680	48.820	2.140	REMOVE TEMPORARY EXISTING OUTFALL DRAIN. BREAKOUT EXISTING PIT TO ACCOMMODATE PROPOSED 675Ø PIPE
EXMW2	JUNCTION PIT	4000	2700	1350	44.190	1500	44.294	46.601	2.411	REMOVE EXISTING 1050Ø STUB, BREAK INTO PIT & CONNECT 1350Ø SWD PIPE
3	JUNCTION PIT	1650	900	1350	44.251	1350	44.251	47.564	3.313	REFER TO EDCM STANDARD DRAWING 607. TO BE HAUNCHED UNDER ROAD
				450	44.701					
6	JUNCTION PIT	1650	900	1350	44.383	1350	44.383	47.701	3.318	REFER TO EDCM STANDARD DRAWING 607. TO BE CONVERTED TO GSEP IN FUTURE STAGE. TO BE HAUNCHED UNDER ROAD
				300	45.433					
7	JUNCTION PIT	1650	900	1350	44.533	1350	44.533	47.843	3.310	REFER TO EDCM STANDARD DRAWING 607. TO BE CONVERTED TO GSEP IN FUTURE STAGE. TO BE HAUNCHED UNDER ROAD
8	JUNCTION PIT	1650	900	1350	44.570	1350	44.570	47.926	3.357	REFER TO EDCM STANDARD DRAWING 607. TO BE CONVERTED TO GSEP IN FUTURE STAGE. TO BE HAUNCHED UNDER ROAD
				450	44.620					
9	JUNCTION PIT	1650	1200	1200	44.624	1350	44.624	48.049	3.426	REFER TO EDCM STANDARD DRAWING 607. TO BE HAUNCHED UNDER ROAD
				675	45.299					
11	JUNCTION PIT	1500	900	1200	44.671	1200	44.671	48.258	3.587	REFER TO EDCM STANDARD DRAWING 607. PROVIDE CLASS D HEAVY DUTY COVER. TO BE CONVERTED TO GSEP IN FUTURE STAGE. TO BE HAUNCHED UNDER ROAD
				300	45.571					
12	JUNCTION PIT	1650	1500	1050	44.912	1200	44.762	48.043	3.281	REFER TO MW STD 7251/08/408 & MW STD 7251/08/409. TO BE HAUNCHED UNDER ROAD
				750	44.812					
13	JUNCTION PIT	1650	1650	1050	45.005	1050	44.955	47.883	2.928	REFER TO MW STD 7251/08/408 & MW STD 7251/08/409. TO BE HAUNCHED UNDER ROAD. TO BE CONVERTED TO GSEP IN FUTURE STAGE.
				900	45.005					
14	JUNCTION PIT	1350	900	900	45.170	1050	45.120	47.985	2.864	REFER TO EDCM STANDARD DRAWING 607. TO BE CONVERTED TO GSEP IN FUTURE STAGE. TO BE HAUNCHED UNDER ROAD
15	JUNCTION PIT	1050	900	825	45.492	900	45.417	48.231	2.814	REFER TO EDCM STANDARD DRAWING 607. TO BE CONVERTED TO GSEP IN FUTURE STAGE. TO BE HAUNCHED UNDER ROAD
				300	46.017					
16	JUNCTION PIT	1050	900	750	45.994	825	45.944	48.608	2.664	REFER TO EDCM STANDARD DRAWING 607
				300	46.469					
17	JUNCTION PIT	1050	900	750	46.080	750	46.030	48.540	2.510	REFER TO EDCM STANDARD DRAWING 607. TO BE CONVERTED TO GSEP IN FUTURE STAGE
				300	46.480					
18	GRATED SIDE ENTRY PIT	1050	900	675	46.360	750	46.285	48.710	2.425	REFER TO EDCM STANDARD DRAWING 607
				300	46.735					
19	JUNCTION PIT	900	900	675	46.714	675	46.714	48.845	2.130	REFER TO EDCM STANDARD DRAWING 607. BREAK INTO EXISTING PIPE AND CONSTRUCT PIT
				225	47.164					
20	JUNCTION PIT	900	1200	600	45.574	675	45.499	48.083	2.583	REFER TO EDCM STANDARD DRAWING 607
21	JUNCTION PIT	900	900	600	45.737	600	45.687	48.139	2.452	REFER TO EDCM STANDARD DRAWING 607
				450	45.837					
22	JUNCTION PIT	900	900	600	46.168	600	46.118	48.271	2.153	REFER TO EDCM STANDARD DRAWING 607. PROVIDE PIT DEFLECTOR IN FLOOR. TO BE CONVERTED TO GSEP IN FUTURE STAGE
				375	46.343					
23	JUNCTION PIT	750	900	525	46.274	600	46.199	48.271	2.072	REFER TO EDCM STANDARD DRAWING 607. PROVIDE PIT DEFLECTOR IN FLOOR. TO BE CONVERTED TO GSEP IN FUTURE STAGE
24	JUNCTION PIT	750	900	525	46.461	525	46.411	48.452	2.041	REFER TO EDCM STANDARD DRAWING 607. TO BE CONVERTED TO GSEP IN FUTURE STAGE
25	JUNCTION PIT	750	900	525	46.743	525	46.693	48.799	2.106	REFER TO EDCM STANDARD DRAWING 607. TO BE CONVERTED TO GSEP IN FUTURE STAGE
26	GRATED SIDE ENTRY PIT	750	900	300	47.203	525	46.978	49.263	2.284	REFER TO EDCM STANDARD DRAWING 601 & 607
				450	47.053					
27	GRATED SIDE ENTRY PIT	600	900			300	48.168	49.770	1.602	REFER TO EDCM STANDARD DRAWING 601 & 605
28	JUNCTION PIT	600	900	450	47.132	450	47.082	49.263	2.181	REFER TO EDCM STANDARD DRAWING 605
29	JUNCTION PIT	900	900	450	47.301	450	47.251	49.514	2.263	REFER TO EDCM STANDARD DRAWING 607
30	GRATED SIDE ENTRY PIT	750	900	300	47.618	300	47.568	49.646	2.078	REFER TO EDCM STANDARD DRAWING 601 & 607
31	GRATED SIDE ENTRY PIT	600	900	300	47.926	300	47.876	49.742	1.866	REFER TO EDCM STANDARD DRAWING 601 & 605
32	GRATED SIDE ENTRY PIT	900	900	300	47.491	450	47.341	49.721	2.381	REFER TO EDCM STANDARD DRAWING 601 & 607
				375	47.416					
33	GRATED SIDE ENTRY PIT	600	900	300	48.163	300	48.113	49.998	1.885	REFER TO EDCM STANDARD DRAWING 605
34	JUNCTION PIT	600	900	300	48.264	300	48.214	50.129	1.915	REFER TO EDCM STANDARD DRAWING 605
35	JUNCTION PIT	600	900			300	48.426	49.718	1.293	REFER TO EDCM STANDARD DRAWING 605
36	GRATED SIDE ENTRY PIT	750	900	300	47.528	375	47.453	49.721	2.269	REFER TO EDCM STANDARD DRAWING 601 & 607. TO BE HAUNCHED UNDER ROAD
				300	47.503					
				225	47.603					
36AEP	ENDPIPE					225	47.650	49.822	2.172	BLANK OFF ENDPIPE WITH MARINE GRADE PLY BOARD FOR FUTURE CONNECTION
37	JUNCTION PIT	600	900	300	48.059	300	48.009	49.884	1.875	REFER TO EDCM STANDARD DRAWING 605
				225	48.084					
38	JUNCTION PIT	600	900			300	48.471	50.267	1.795	REFER TO EDCM STANDARD DRAWING 605
39	JUNCTION PIT	600	900	225	49.318	225	49.268	50.179	0.911	REFER TO EDCM STANDARD DRAWING 605
40	JUNCTION PIT	600	900			225	49.485	50.349	0.864	REFER TO EDCM STANDARD DRAWING 605
41	GRATED SIDE ENTRY PIT	600	900			300	46.853	48.707	1.854	REFER TO EDCM STANDARD DRAWING 601 & 605
42	JUNCTION PIT	600	900			225	48.289	49.804	1.515	REFER TO EDCM STANDARD DRAWING 605
43	JUNCTION PIT	600	900	300	48.033	300	47.983	49.890	1.907	REFER TO EDCM STANDARD DRAWING 605
44	GRATED SIDE ENTRY PIT	600	900			300	48.061	49.873	1.811	REFER TO EDCM STANDARD DRAWING 601 & 605


NOTE: ALL HAUNCHED PITS TO BE HAUNCHED UNDER NATURE STRIP UNLESS SPECIFIED IN PIT SCHEDULE

PIT SETOUT CO-ORDINATES


NAME	POINT	EASTING	NORTHING
3	B	298313.493	5812714.127
6	B	298256.646	5812687.756
7	B	298181.919	5812694.149
8	B	298163.707	5812695.707
9	B	298136.855	5812698.004
11	B	298119.243	5812687.467
12	B	298115.335	5812641.784
13	B	298103.244	5812632.781
14	B	298072.884	5812635.379
15	B	297999.324	5812641.672
16	B	297915.908	5812648.808
17	B	297906.912	5812649.578
20	B	298137.580	5812706.473
21	B	298117.652	5812708.178
22	B	298092.943	5812710.292
23	B	298092.218	5812701.822
24	B	298055.295	5812704.981
25	B	297986.008	5812710.909
36AEP	C	297859.891	5812738.409
38	A	297870.130	5812802.369
39	A	297833.323	5812756.339
40	A	297836.903	5812798.186
42	B	297821.607	5812724.974
43	A	297802.346	5812741.692

PIPE SPLAY SCHEDULE


DOWNSTREAM NO.	UPSTREAM NO.	DIAMETER	RADIUS	ANGLE	TOTAL ARC LENGTH	PIPE UNIT EFFECTIVE LENGTH	MIN NO. OF PIPES	JOINTING METHOD
1TP	2TP	1350	14	69.95	17.091	2.136	8	FLUSH JOINT
5TP	4TP	1350	14	43.25	10.567	2.113	5	FLUSH JOINT
10TP	11	1200	12	90.00	18.857	2.357	8	FLUSH JOINT
12	12ATP	1050	10	90.00	15.721	2.246	7	FLUSH JOINT




TYPICAL DRAINAGE PIT SETOUT POINT 'A'
JUNCTION PIT/ EASEMENT PIT
NOT TO SCALE



HAUNCHED PITS UNDER NATURE STRIP
NOT TO SCALE



TYPICAL DRAINAGE PIT SETOUT POINT 'B'
SIDE ENTRY PIT / JUNCTION PIT
NOT TO SCALE




HAUNCHED PITS UNDER PAVEMENT
NOT TO SCALE

Planning and Environment Act 1987
Wyndham Planning Scheme

Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 25/03/2025

file name: 309442CR600.dwg, layout name: CR603, plotted by: Thanh Nguyen, file location: \\spiiremedia\data\309442.dwg, plot date: 19/03/2025 3:42 PM, sheet: 15 of 17, sheets

0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
D	DRAINAGE PIT SCHEDULE & SETOUT COORDINATES AMENDED	G.K	28/01/25
C	DRAINAGE PIT SCHEDULE & PIT SETOUT COORDINATES AMENDED; PIPE SPLAY SCHEDULE & TYPICAL SETOUT ADDED	G.K	18/12/24
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24
Rev	Amendments	Approved	Date



ISO 9001
ISO 45001
ISO 14001

System Certified

© Spiire Australia Pty Ltd All Rights Reserved
This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

spiire

L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635

Harlow
TARNEIT

Designed
T. NGUYEN

Checked
G. KOHLMAN

Authorised
G. KOHLMAN

Date
01/11/24

HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
DRAINAGE PIT SCHEDULE
WYNDHAM CITY COUNCIL
SIG GROUP

CONSTRUCTION

Drg No
309442CR603

Rev
0

PAVEMENT LAYER	DESCRIPTION	DEPTH (mm)
		TYPE A
ASPHALT WEARING COURSE	SIZE 10 TYPE N C320	30
ASPHALT BASE COURSE	SIZE 10 TYPE N C320	30
PRIMECOAT	PRIME & 10mm SAMI (S 18RF)	10
BASE COURSE	VICROADS CLASS 2 FCR (20mm)	130
UPPER SUBBASE	VICROADS CLASS 3 FCR (20mm)	120
LOWER SUBBASE	VICROADS CLASS 3 FCR (20mm)	120
CAPPING LAYER	VICROADS TYPE A CAPPING LAYER OR APPROVED ALTERNATIVE AS PER TABLE 5 (CBR≥10%, SWELL<15%, K<5X10 ⁻³ m/sec)	150
CONSTRUCTION LAYER	VICROADS TYPE A CAPPING LAYER OR APPROVED ALTERNATIVE AS PER TABLE 5 (CBR≥10%, SWELL<15%, K<5X10 ⁻³ m/sec)	150
TOTAL PAVEMENT DEPTH		740


ROAD NAME	TYPE
TURMERIC STREET	ACCESS STREET LEVEL 1
JIRA CRESCENT	ACCESS STREET LEVEL 1
SPRINGFALL ROAD	ACCESS STREET LEVEL 1



NOTES:

1. SUBGRADE TO CONSIST OF UNIT 3 NATURAL RESIDUAL CLAYS OR CONTROLLED (ENGINEERED) FILL (CBR \geq 2.0%)

**Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 20/10/2025**




THE PAVEMENT DESIGNS SHOWN HERE HAVE BEEN DESIGNED/PROVIDED BY GROUND SCIENCE PTY LTD WHO ARE RESPONSIBLE FOR THE GEOTECHNICAL WORK ON THIS PROJECT. SPIRE IS NOT RESPONSIBLE FOR THE WORK OF GROUND SCIENCE PTY LTD.


THE DESIGN HAS BEEN EXTRACTED FROM THE "GEOTECHNICAL INVESTIGATION" REPORT ON "GEOTECHNICAL INVESTIGATION FOR 860 DERRIMUT ROAD, TARNEIT (DATED 18 OCTOBER 2021, REPORT REFERENCE G4572.1 AA) " & "TECHNICAL MEMORANDUM" REPORT ON "HARLOW ESTATE, STAGE 6, FUTURE BOURNESIDE STREET INTERSECTION (DATED 14 MAY 2025, REPORT REFERENCE G4572.5 AA". THESE DOCUMENTS SHOULD BE REVIEWED TO ENSURE THAT THE DESIGN HAS BEEN ACCURATELY REPRODUCED.

A COPY OF THE DOCUMENTS WILL BE PROVIDED ON REQUEST.



SPiIRE DOES NOT ACCEPT ANY RESPONSIBILITY FOR THE ACCURACY, ADEQUACY OR APPROPRIATENESS OF THE GEOTECHNICAL WORK AND PAVEMENT DESIGNS.
ANY QUERIES IN RESPECT TO THE GEOTECHNICAL WORK AND PAVEMENT DESIGNS SHOULD BE ADDRESSED TO GROUND SCIENCE PTY LTD AND COPIED TO SPiIRE.



LIMIT OF WORKS CONCRETE EDGE STRIP & PAVEMENT INTERFACE DETAIL





LOT REGRADING DETAIL




LOT FILLING AT STAGE BOUNDARY

NOT TO SCALE




SILT CONTROL FOR LOTS




TEMPORARY TURNING AREA DETAIL

NOT TO SCALE



TYPICAL PARKING BAY DETAIL

NOT TO SCALE



STANDARD KERB PROFILES

NOTE: ALL KERB & CHANNEL AS PER EDCM STD DRAWING EDCM 301



2	ROAD NAME & PAVEMENT PROFILE AMENDED	G.K	01/10/25
1	PAVEMENT TYPE B ADDED, PAVEMENT HATCH AMENDED	G.K	23/07/25
0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
C	ROAD TYPE TABLE & SPRINGFALL ROAD PAVEMENT TYPE AMENDED	G.K	18/12/24
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24
Rev	Amendments	Approved	Date

Scale



© Spiire Australia Pty Ltd All Rights Reserved

This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

spiire

L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635



Designed
T. NGUYEN
Authorised
G. KOHLMAN

Checked
G. KOHLMAN
Date
01/11/24

**HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
PAVEMENT AND TYPICAL DETAILS
WYNDHAM CITY COUNCIL
SIG GROUP**

CONSTRUCTION Drg No **309442CR700**

2

SIGNAGE SCHEDULE

REFERENCE NO.	SIGN	COMMENTS
1		STREET NAME PLATES TO BE IN ACCORDANCE WITH HCC SD4/08 & SD4/12, INCLUDING "NO THROUGH ROAD" NOMINATION WHERE APPLICABLE
2		R1-2
3		G9-20
4		D4-5
5		W3-4
6		D4-1-1(R)
7		D4-1-1(L)
8		R5-35(R)

NOTE: STREET SIGNS ARE TO BE MOUNTED ON LIGHT POLES, WITH A COUNCIL APPROVED BRACKET, IN LIEU OF SIGN POLES WHERE THE TWO POLES ARE IN CLOSE PROXIMITY AND WHERE THE STREET SIGN WOULD NOT BE COMPROMISED IN ITS PURPOSE BY THE RELOCATION.

LINEMARKING LEGEND

SYMBOL	DESCRIPTION	REMARK
	CONTINUOUS LANE LINE	100mm WIDE
	HOLDING LINE (GIVEWAY)	600mm LINE, 600mm GAP, 300mm WIDE
	UNI-DIRECTIONAL RRPM	REFER AS174.2.2 - 2009
	TACTILE GROUND SURFACE INDICATORS	REFER AS1428.4.1 - 2009


Planning and Environment Act 1987
Wyndham Planning Scheme

Approved Plan As Required
under Condition 63
Permit No WYP13902/22
Date 20/10/2025



file name: 309442CR800.dwg, layout name: CR800, plotted by: Thanh Nguyen, file location: G:\30\309442\309442\309442.dwg, plot date: 02/10/2025 9:34, A4 Sheet 17 of 17 Sheets

Rev	Amendments	Approved	Date
1	ROAD NAME AMENDED	G.K	01/10/25
0	ISSUED FOR CONSTRUCTION	G.K	19/03/25
D	SIGNAGE ADDED	G.K	28/01/25
C	LINEMARKING LEGEND AMENDED	G.K	18/12/24
B	ISSUED FOR TENDER	G.K	16/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24



© Spiire Australia Pty Ltd All Rights Reserved
This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.




L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635




Designed T. NGUYEN	Checked G. KOHLMAN
Authorised G. KOHLMAN	Date 01/11/24

HARLOW ESTATE
STAGE 6
ROAD AND DRAINAGE
SIGNAGE AND LINEMARKING
WYNDHAM CITY COUNCIL
SIG GROUP

CONSTRUCTION Drg No 309442CR800 Rev 1



C	CATCHMENTS C, D, F & P AMENDED	G.K	28/01/25	
B	CATCHMENTS AMENDED	G.K	18/12/24	
A	ISSUED TO COUNCIL	G.K	01/11/24	
Rev	Amendments	Approved	Date	



System Certified

© Spiire Australia Pty Ltd All Rights Reserved
This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635

Designed
T. NGUYEN
Authorised
G. KOHLMAN
Checked
G. KOHLMAN
Date
01/11/24

**HARLOW ESTATE
STAGE 6
DRAINAGE COMPUTATIONS
100YR CATCHMENT PLAN
WYNDHAM CITY COUNCIL
SIG GROUP**

PRELIMINARY Drg No 309442CD500 Rev C

Fraction Impervious		C100	C5	C10
Road Runoff f =	0.6	0.709	0.561	0.591
Residential Lot Runoff f =	0.8	0.894	0.708	0.745
Commerical Runoff f =	0.9	0.987	0.782	0.823
Open Space Runoff f =	0.7	0.802	0.635	0.668

Catchment	AREA (Ha)					Fraction Impervious (f)	Weighted Runoff	Weighted Runoff	Weighted Runoff
	Road	Lots	Commerical	Open Space	TOTAL		C100	C5	C10
A	0.14	0.42			0.55	0.75	0.849	0.672	0.707
B	0.60	1.52			2.12	0.74	0.842	0.667	0.702
C	0.05	0.14			0.19	0.74	0.842	0.666	0.701
D	0.09	0.02			0.12	0.64	0.743	0.588	0.619
E	0.38	0.74		0.009	1.13	0.73	0.831	0.658	0.693
F	0.36	0.68			1.05	0.73	0.830	0.657	0.692
G	0.30	0.55			0.85	0.73	0.830	0.657	0.691
H	0.12	0.12		0.002	0.24	0.70	0.800	0.633	0.667
I	0.33	0.41		0.032	0.77	0.71	0.811	0.642	0.676
J	0.21	0.55			0.75	0.75	0.844	0.668	0.703
K	0.47	0.42			0.89	0.69	0.797	0.631	0.664
L	0.23	0.28		1.82	2.33	0.70	0.803	0.636	0.669
M	0.20	0.25			0.44	0.71	0.811	0.642	0.676
N	2.31	4.01	1.01	1.68	9.01	0.74	0.840	0.665	0.700
O	0.17	0.50			0.67	0.75	0.847	0.671	0.706
P	0.26	0.49			0.75	0.73	0.830	0.657	0.692
Q	0.14	0.38			0.52	0.75	0.844	0.668	0.703
R	0.23	0.11			0.34	0.67	0.770	0.609	0.642
S	0.18	0.22			0.40	0.71	0.809	0.641	0.674
T	0.27	0.55			0.82	0.73	0.834	0.660	0.695
U	0.12	0.11			0.24	0.70	0.798	0.632	0.665
V	0.40	0.66		0.07	1.14	0.72	0.823	0.651	0.686

Annual Exceedance Probability (%)

ARI	1	2	5	10	20	50	100
C0	0.30852	0.44522	0.8061217	1.0110151	1.190063	1.4027599	1.5511954
C1	0.71811	0.70162	0.6798835	0.66928446	0.659043	0.6401919	0.6328916
C2	0.11054	0.12434	0.1372764	0.14462879	0.153391	0.1754506	0.18463588
C3	-0.09473	-0.09741	-0.096018	-0.0965306	-0.09872	-0.108387	-0.11294799
C4	0.02157	0.02135	0.0195062	0.01904607	0.019171	0.0212029	0.022312067
C5	-0.00209	-0.002	-0.001683	-0.0015911	-0.00158	-0.001782	-0.0019084
C6	7.37E-05	6.82E-05	5.25E-05	4.77E-05	4.64E-05	5.42E-05	5.95E-05


100yr URBAN ARI Drainage Calculations

DEVELOPED CATCHMENT

Catchment	Section	Additional Catchments				Area (ha)	ΣA (ha)	C100	C5	Ae 100 (ha)	Ae 5 (ha)	ΣC100	ΣC5	ΣAe 100 (ha)	ΣAe 5 (ha)	Flow Length (m)	Velocity 100y (m/s)	Velocity 5y (m/s)	Tc 100 (mins)	Tc 5 (mins)	Int 100 (mm/hr)	Int 5 (mm/hr)	Q100 m3/s	Q5 m3/s	Q5gap m3/s	Comments
A	A					0.554	0.554	0.85	0.67	0.47	0.37	0.85	0.67	0.47	0.37	129	0.62	1.5	8.45	6.43	146.80	78.23	0.192	0.081	0.111	
B	B	A				2.115	2.669	0.84	0.67	1.78	1.41	0.84	0.67	2.25	1.78	436	0.87	1.5	13.37	9.84	117.78	64.95	0.737	0.322	0.415	Includes Catchment A
C	C					0.190	0.190	0.84	0.67	0.16	0.13	0.84	0.67	0.16	0.13	55	1.13	1.5	5.81	5.61	170.59	82.46	0.076	0.029	0.047	
D	D	B	C			0.115	2.974	0.74	0.59	0.09	0.07	0.84	0.66	2.50	1.98	44	0.74	1.5	14.37	10.33	113.40	63.46	0.786	0.348	0.438	Includes Catchments A-C
E	E	D				1.133	4.107	0.83	0.66	0.94	0.75	0.84	0.66	3.44	2.72	146	0.85	1.5	17.22	11.96	102.67	59.02	0.981	0.446	0.534	Includes Catchments A-D
F	F					1.046	1.046	0.83	0.66	0.87	0.69	0.83	0.66	0.87	0.69	272	0.73	1.5	11.18	8.02	128.96	71.33	0.311	0.136	0.175	
G	G	F				0.850	1.896	0.83	0.66	0.71	0.56	0.83	0.66	1.57	1.25	199	1.21	1.5	13.91	10.23	115.38	63.76	0.504	0.221	0.284	Includes Catchment F
H	H	E	G			0.242	6.245	0.80	0.63	0.19	0.15	0.83	0.66	5.21	4.12	89	0.64	1.5	19.53	12.94	95.54	56.65	1.381	0.648	0.733	Includes Catchments A-G
I	I	H				0.767	7.012	0.81	0.64	0.62	0.49	0.83	0.66	5.83	4.61	175	0.64	1.5	24.07	14.89	84.37	52.56	1.366	0.674	0.692	Includes Catchments A-H
J	J					0.751	0.751	0.84	0.67	0.63	0.50	0.84	0.67	0.63	0.50	151	0.67	1.5	8.75	6.68	144.56	77.07	0.254	0.107	0.147	
K	K	J				0.887	1.638	0.80	0.63	0.71	0.56	0.82	0.65	1.34	1.06	60	1.02	1.5	9.73	7.34	137.76	74.09	0.513	0.218	0.295	Includes Catchment J
L	L					2.333	2.333	0.80	0.64	1.87	1.48	0.80	0.64	1.87	1.48	274	0.94	1.5	9.88	8.04	136.77	71.24	0.712	0.294	0.418	
M	M					0.443	0.443	0.81	0.64	0.36	0.28	0.81	0.64	0.36	0.28	143	0.57	1.5	9.15	6.59	141.69	77.49	0.141	0.061	0.080	
N	N	L	M			9.014	11.790	0.84	0.66	7.57	5.99	0.83	0.66	9.80	7.76	796	0.68	1.5	24.42	13.84	83.61	54.67	2.277	1.179	1.099	Includes Catchments L & M
O	O					0.670	0.670	0.85	0.67	0.57	0.45	0.85	0.67	0.57	0.45	180	0.67	1.5	9.47	7.00	139.50	75.60	0.220	0.094	0.126	
P	P	N	O			0.753	13.213	0.83	0.66	0.63	0.49	0.83	0.66	11.00	8.71	105	0.62	1.5	27.25	15.01	78.15	52.33	2.387	1.266	1.122	Includes Catchments L-O
Q	Q	P				0.515	13.728	0.84	0.67	0.43	0.34	0.83	0.66	11.43	9.05	78	1.47	1.5	28.13	15.88	76.61	50.74	2.433	1.276	1.157	Includes Catchments L-P
R	R					0.335	0.335	0.77	0.61	0.26	0.20	0.77	0.61	0.26	0.20	108	0.57	1.5	8.14	6.20	149.24	79.38	0.107	0.045	0.062	
S	S	R				0.398	0.733	0.81	0.64	0.32	0.25	0.79	0.63	0.58	0.46	77	1.21	1.5	9.20	7.06	141.38	75.35	0.228	0.096	0.132	Includes Catchment R
T	T					0.818	0.818	0.83	0.66	0.68	0.54	0.83	0.66	0.68	0.54	183	1.72	1.5	6.77	7.03	160.96	75.45	0.305	0.113	0.192	
U	U	S	T			0.235	1.786	0.80	0.63	0.19	0.15	0.81	0.64	1.45	1.15	76	1.44	1.5	10.08	7.90	135.53	71.81	0.546	0.229	0.317	Includes Catchments R-T
V	V	Q	U			1.135	16.649	0.82	0.65	0.93	0.74	0.83	0.66	13.82	10.94	121	0.81	1.5	30.62	17.22	72.61	48.48	2.787	1.473	1.314	Includes Catchments L-U

file name 309442CD501.dwg, layout name CD501, plotted by Thanh Nguyen, file location G:\30\309442\CD501\ACAD plot date 18/03/2025 10:57 AM Sheet 1 of 1 Sheets

A	ISSUED TO COUNCIL	G.K	01/11/24	
Rev	Amendments	Approved	Date	



System Certified

© Spiire Australia Pty Ltd All Rights Reserved
This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635



Designed T. NGUYEN	Checked G. KOHLMAN
Authorised G. KOHLMAN	Date 01/11/24


HARLOW ESTATE
STAGE 6
DRAINAGE COMPUTATIONS
100YR CATCHMENT CALCULATIONS
WYNDHAM CITY COUNCIL
SIG GROUP

PRELIMINARY Drg No **309442CD501** Rev **A**

file name: 309442CD503.dwg, layout name: CD503, plotted by: Thach Nguyen,
file location: G:\30309442\Civil\12DPC CONVEY\SECTION L.dwg, plot date: 18/03/2025 10:58 AM, Sheet: 1 of 1 Sheets

PROJECT: SECTION I
HELIOTROPE COURT (CH154.38)
Print-out date: 15/01/2025 - Time: 8:30
Data File: G:\30309442\Civil\12DPC CONVEY\SECTION I.dwt

1. CROSS-SECTION:



2. DISCHARGE INFORMATION:

100 year (1%) storm event

Total discharge = 0.692 cumecs

There is no pipe discharge
Overland / Channel / Watercourse discharge = 0.692 cumecs

3. RESULTS: Water surface elevation = 47.377m

High Flow Channel grade = 1 in 200, Main Channel / Low Flow Channel grade = 1 in 200.


	LEFT OVERBANK	MAIN CHANNEL	RIGHT OVERBANK	TOTAL CROSS-SECTION
Discharge (cumecs):	0.00	0.75	0.00	0.75
D(Max) = Max. Depth (m):	0.00	0.22	0.00	0.22
D(Ave) = Ave. Depth (m):	0.00	0.10	0.00	0.10
V = Ave. Velocity (m/s):	0.00	0.64	0.00	0.64
D(Max) x V (cumecs/m):	0.00	0.14	0.00	0.14
D(Ave) x V (cumecs/m):	0.00	0.06	0.00	0.06
Froude Number:	0.00	0.65	0.00	0.65
Area (m ²):	0.00	1.16	0.00	1.16
Wetted Perimeter (m):	0.00	12.06	0.00	12.06
Flow Width (m):	0.00	11.82	0.00	11.82
Hydraulic Radius (m):	0.00	0.10	0.00	0.10
Composite Manning's n:	0.000	0.023	0.000	0.023
Split Flow?	-	-	-	No

4. CROSS-SECTION DATA:

SEGMENT NO.	LEFT HAND POINT CHAINAGE (m)	R.L. (m)	RIGHT HAND POINT CHAINAGE (m)	R.L. (m)	MANNING'S N
1	-9.357	47.653	-8.000	47.427	0.013
2	-8.000	47.427	-7.950	47.425	0.035
3	-7.950	47.425	-6.450	47.395	0.035
4	-6.450	47.395	-3.800	47.307	0.013
5	-3.800	47.307	-3.690	47.307	0.013
6	-3.690	47.307	-3.650	47.157	0.013
7	-3.650	47.157	-3.200	47.197	0.013
8	-3.200	47.197	0.000	47.304	0.013
9	0.000	47.304	3.200	47.197	0.013
10	3.200	47.197	3.650	47.157	0.013
11	3.650	47.157	3.690	47.307	0.013
12	3.690	47.307	3.800	47.307	0.013
13	3.800	47.307	6.450	47.395	0.035
14	6.450	47.395	7.950	47.425	0.013
15	7.950	47.425	8.000	47.427	0.035
16	8.000	47.427	9.000	47.594	0.035

PROJECT: SECTION M
SALVIAS ROAD (CH148.29)
Print-out date: 20/01/2025 - Time: 10:38
Data File: G:\30309442\Civil\12DPC CONVEY\SECTION M.dwt

1. CROSS-SECTION:



2. DISCHARGE INFORMATION:

100 year (1%) storm event

Total discharge = 0.08 cumecs

There is no pipe discharge
Overland / Channel / Watercourse discharge = 0.080 cumecs

3. RESULTS: Water surface elevation = 48.052m

High Flow Channel grade = 1 in 200, Main Channel / Low Flow Channel grade = 1 in 200.


	LEFT OVERBANK	MAIN CHANNEL	RIGHT OVERBANK	TOTAL CROSS-SECTION
Discharge (cumecs):	0.00	0.08	0.00	0.08
D(Max) = Max. Depth (m):	0.00	0.09	0.00	0.09
D(Ave) = Ave. Depth (m):	0.00	0.04	0.00	0.04
V = Ave. Velocity (m/s):	0.00	0.57	0.00	0.57
D(Max) x V (cumecs/m):	0.00	0.05	0.00	0.05
D(Ave) x V (cumecs/m):	0.00	0.02	0.00	0.02
Froude Number:	0.00	0.97	0.00	N/A
Area (m ²):	0.00	0.14	0.00	0.14
Wetted Perimeter (m):	0.00	4.08	0.00	4.08
Flow Width (m):	0.00	3.94	0.00	3.94
Hydraulic Radius (m):	0.00	0.03	0.00	0.03
Composite Manning's n:	0.000	0.013	0.000	N/A
Split Flow?	-	-	-	Yes

4. CROSS-SECTION DATA:

SEGMENT NO.	LEFT HAND POINT CHAINAGE (m)	R.L. (m)	RIGHT HAND POINT CHAINAGE (m)	R.L. (m)	MANNING'S N
1	-8.000	48.232	-7.950	48.231	0.035
2	-7.950	48.231	-6.450	48.201	0.013
3	-6.450	48.201	-3.800	48.112	0.035
4	-3.800	48.112	-3.690	48.112	0.013
5	-3.690	48.112	-3.650	47.962	0.013
6	-3.650	47.962	-3.200	48.002	0.013
7	-3.200	48.002	0.000	48.109	0.013
8	0.000	48.109	3.200	48.002	0.013
9	3.200	48.002	3.650	47.962	0.013
10	3.650	47.962	3.690	48.112	0.013
11	3.690	48.112	3.800	48.112	0.013
12	3.800	48.112	6.450	48.201	0.035
13	6.450	48.201	7.950	48.231	0.013
14	7.950	48.231	8.000	48.232	0.035

PROJECT: SECTION J
TOMATILLO CIRCUIT (CH19.132)
Print-out date: 14/10/2024 - Time: 12:45
Data File: G:\30309442\Civil\12DPC CONVEY\SECTION J.dwt

1. CROSS-SECTION:



2. DISCHARGE INFORMATION:

100 year (1%) storm event

Total discharge = 0.147 cumecs

There is no pipe discharge
Overland / Channel / Watercourse discharge = 0.147 cumecs

3. RESULTS: Water surface elevation = 47.193m

High Flow Channel grade = 1 in 200, Main Channel / Low Flow Channel grade = 1 in 200.


	LEFT OVERBANK	MAIN CHANNEL	RIGHT OVERBANK	TOTAL CROSS-SECTION
Discharge (cumecs):	0.00	0.15	0.00	0.15
D(Max) = Max. Depth (m):	0.00	0.11	0.00	0.11
D(Ave) = Ave. Depth (m):	0.00	0.04	0.00	0.04
V = Ave. Velocity (m/s):	0.00	0.67	0.00	0.67
D(Max) x V (cumecs/m):	0.00	0.07	0.00	0.07
D(Ave) x V (cumecs/m):	0.00	0.03	0.00	0.03
Froude Number:	0.00	1.01	0.00	N/A
Area (m ²):	0.00	0.23	0.00	0.23
Wetted Perimeter (m):	0.00	5.32	0.00	5.32
Flow Width (m):	0.00	5.15	0.00	5.15
Hydraulic Radius (m):	0.00	0.04	0.00	0.04
Composite Manning's n:	0.000	0.013	0.000	N/A
Split Flow?	-	-	-	Yes

4. CROSS-SECTION DATA:

SEGMENT NO.	LEFT HAND POINT CHAINAGE (m)	R.L. (m)	RIGHT HAND POINT CHAINAGE (m)	R.L. (m)	MANNING'S N
1	-8.000	47.353	-7.950	47.351	0.035
2	-7.950	47.351	-6.450	47.321	0.013
3	-6.450	47.321	-3.800	47.233	0.035
4	-3.800	47.233	-3.690	47.233	0.013
5	-3.690	47.233	-3.650	47.083	0.013
6	-3.650	47.083	-3.200	47.123	0.013
7	-3.200	47.123	0.000	47.230	0.013
8	0.000	47.230	3.200	47.123	0.013
9	3.200	47.123	3.650	47.083	0.013
10	3.650	47.083	3.690	47.233	0.013
11	3.690	47.233	3.800	47.233	0.013
12	3.800	47.233	6.450	47.321	0.035
13	6.450	47.321	7.950	47.351	0.013
14	7.950	47.351	8.000	47.353	0.035

PROJECT: SECTION N
SPRINGFALL ROAD (CH314.29)
Print-out date: 10/12/2024 - Time: 3:21
Data File: G:\30309442\Civil\12DPC CONVEY\SECTION N.dwt

1. CROSS-SECTION:



2. DISCHARGE INFORMATION:

100 year (1%) storm event

Total discharge = 1.1 cumecs

There is no pipe discharge
Overland / Channel / Watercourse discharge = 1.099 cumecs

3. RESULTS: Water surface elevation = 47.986m

High Flow Channel grade = 1 in 300, Main Channel / Low Flow Channel grade = 1 in 300.


	LEFT OVERBANK	MAIN CHANNEL	RIGHT OVERBANK	TOTAL CROSS-SECTION
Discharge (cumecs):	0.00	1.11	0.00	1.11
D(Max) = Max. Depth (m):	0.00	0.28	0.00	0.28
D(Ave) = Ave. Depth (m):	0.00	0.13	0.00	0.13
V = Ave. Velocity (m/s):	0.00	0.68	0.00	0.68
D(Max) x V (cumecs/m):	0.00	0.19	0.00	0.19
D(Ave) x V (cumecs/m):	0.00	0.09	0.00	0.09
Froude Number:	0.00	0.61	0.00	0.61
Area (m ²):	0.00	1.63	0.00	1.63
Wetted Perimeter (m):	0.00	12.95	0.00	12.95
Flow Width (m):	0.00	12.71	0.00	12.71
Hydraulic Radius (m):	0.00	0.13	0.00	0.13
Composite Manning's n:	0.000	0.021	0.000	0.021
Split Flow?	-	-	-	No

4. CROSS-SECTION DATA:

SEGMENT NO.	LEFT HAND POINT CHAINAGE (m)	R.L. (m)	RIGHT HAND POINT CHAINAGE (m)	R.L. (m)	MANNING'S N
1	-10.910	48.206	-10.000	48.054	0.013
2	-10.000	48.054	-9.950	48.053	0.035
3	-9.950	48.053	-8.450	48.023	0.013
4	-8.450	48.023	-6.450	47.856	0.035
5	-6.450	47.856	-5.340	47.856	0.013
6	-5.340	47.856	-5.300	47.706	0.013
7	-5.300	47.706	-4.850	47.746	0.013
8	-4.850	47.746	0.000	47.908	0.013
9	0.000	47.908	3.200	47.801	0.013
10	3.200	47.801	3.650	47.761	0.013
11	3.650	47.761	3.690	47.911	0.013
12	3.690	47.911	3.800	47.911	0.013
13	3.800	47.911	6.450	48.088	0.035
14	6.450	48.088	7.950	48.118	0.013
15	7.950	48.118	8.000	48.119	0.035
16	8.000	48.119	9.155	48.312	0.035

PROJECT: SECTION K
TOMATILLO CIRCUIT (CH24.50)
Print-out date: 01/11/2024 - Time: 9:05
Data File: G:\30309442\Civil\12DPC CONVEY\SECTION K.dwt

1. CROSS-SECTION:



2. DISCHARGE INFORMATION:

100 year (1%) storm event

Total discharge = 0.295 cumecs

There is no pipe discharge
Overland / Channel / Watercourse discharge = 0.295 cumecs

3. RESULTS: Water surface elevation = 46.806m

High Flow Channel grade = 1 in 111.29, Main Channel / Low Flow Channel grade = 1 in 111.29.


	LEFT OVERBANK	MAIN CHANNEL	RIGHT OVERBANK	TOTAL CROSS-SECTION
Discharge (cumecs):	0.00	0.36	0.00	0.36
D(Max) = Max. Depth (m):	0.00	0.13	0.00	0.13
D(Ave) = Ave. Depth (m):	0.00	0.05	0.00	0.05
V = Ave. Velocity (m/s):	0.00	1.02	0.00	1.02
D(Max) x V (cumecs/m):	0.00	0.13	0.00	0.13
D(Ave) x V (cumecs/m):	0.00	0.06	0.00	0.06
Froude Number:	0.00	N/A	0.00	N/A
Area (m ²):	0.00	0.35	0.00	0.35
Wetted Perimeter (m):	0.00	6.61	0.00	6.61
Flow Width (m):	0.00	6.40	0.00	6.40
Hydraulic Radius (m):	0.00	0.05	0.00	0.05
Composite Manning's n:	0.000	0.013	0.000	N/A
Split Flow?	-	-	-	Yes

4. CROSS-SECTION DATA:

SEGMENT NO.	LEFT HAND POINT CHAINAGE (m)	R.L. (m)	RIGHT HAND POINT CHAINAGE (m)	R.L. (m)	MANNING'S N
1	-8.000	46.946	-7.950	46.944	0.035
2	-7.950	46.944	-6.450	46.914	0.013
3	-6.450	46.914	-3.800	46.826	0.035
4	-3.800	46.826	-3.690	46.826	0.013
5	-3.690	46.826	-3.650	46.676	0.013
6	-3.650	46.676	-3.200	46.716	0.013
7	-3.200	46.716	0.000	46.822	0.013
8	0.000	46.822	3.200	46.716	0.013
9	3.200	46.716	3.650	46.676	0.013
10	3.650	46.676	3.690	46.826	0.013
11	3.690	46.826	3.800	46.826	0.013
12	3.800	46.826	6.450	46.932	0.035
13	6.450	46.932	7.950	46.962	0.013
14	7.950	46.962	8.000	46.963	0.035

PROJECT: SECTION O
LUMPINI ROAD (CH148.29)
Print-out date: 10/12/2024 - Time: 3:24
Data File: G:\30309442\Civil\12DPC CONVEY\SECTION O.dwt

1. CROSS-SECTION:



2. DISCHARGE INFORMATION:

100 year (1%) storm event

Total discharge = 0.126 cumecs


There is no pipe discharge
Overland / Channel / Watercourse discharge = 0.126 cumecs

3. RESULTS: Water surface elevation = 47.992m

High Flow Channel grade = 1 in 200, Main Channel / Low Flow Channel grade = 1 in 200.

	LEFT OVER
--	--------------

file name: 309442CD500.dwg, layout name: CDS04, plotted by: Tash Nguyen,
file location: G:\30\309442\Civil\12DPC CONVEY\SECTION Q.dwg, 18/03/2025, 10:58 AM, Sheet 1 of 1 Sheets



2. DISCHARGE INFORMATION:

100 year (1%) storm event

Total discharge = 1.16 cumecs

There is no pipe discharge
Overland / Channel / Watercourse discharge = 1.157 cumecs


3. RESULTS: Water surface elevation = 46.607m

High Flow Channel grade = 1 in 41.667, Main Channel / Low Flow Channel grade = 1 in 41.667.

	LEFT OVERBANK	MAIN CHANNEL	RIGHT OVERBANK	TOTAL CROSS-SECTION
Discharge (cumecs):	0.00	1.23	0.00	1.23
D(Max) = Max. Depth (m):	0.00	0.19	0.00	0.19
D(Ave) = Ave. Depth (m):	0.00	0.09	0.00	0.09
V = Ave. Velocity (m/s):	0.00	1.47	0.00	1.47
D(Max) x V (cumecs/m):	0.00	0.28	0.00	0.28
D(Ave) x V (cumecs/m):	0.00	0.13	0.00	0.13
Froude Number:	0.00	1.61	0.00	1.61
Area (m ²):	0.00	0.84	0.00	0.84
Wetted Perimeter (m):	0.00	10.04	0.00	10.04
Flow Width (m):	0.00	9.80	0.00	9.80
Hydraulic Radius (m):	0.00	0.08	0.00	0.08
Composite Manning's n:	0.000	0.020	0.000	0.020
Split Flow?	-	-	-	No

4. CROSS-SECTION DATA:

SEGMENT NO.	LEFT HAND POINT CHAINAGE (m)	R.L. (m)	RIGHT HAND POINT CHAINAGE (m)	R.L. (m)	MANNING'S N
1	-9.200	46.904	-8.000	46.704	0.013
2	-8.000	46.704	-7.950	46.703	0.035
3	-7.950	46.703	-6.450	46.673	0.013
4	-6.450	46.673	-3.800	46.567	0.035
5	-3.800	46.567	-3.690	46.567	0.013
6	-3.690	46.567	-3.650	46.417	0.013
7	-3.650	46.417	-3.200	46.457	0.013
8	-3.200	46.457	0.000	46.563	0.013
9	0.000	46.563	3.200	46.457	0.013
10	3.200	46.457	3.650	46.417	0.013
11	3.650	46.417	3.690	46.567	0.013
12	3.690	46.567	3.800	46.567	0.013
13	3.800	46.567	6.450	46.655	0.035
14	6.450	46.655	7.950	46.685	0.013
15	7.950	46.685	8.000	46.687	0.035
16	8.000	46.687	9.000	46.853	0.035



2. DISCHARGE INFORMATION:

100 year (1%) storm event

Total discharge = 0.192 cumecs

There is no pipe discharge
Overland / Channel / Watercourse discharge = 0.192 cumecs


3. RESULTS: Water surface elevation = 45.671m

High Flow Channel grade = 1 in 22.222, Main Channel / Low Flow Channel grade = 1 in 22.222.

	LEFT OVERBANK	MAIN CHANNEL	RIGHT OVERBANK	TOTAL CROSS-SECTION
Discharge (cumecs):	0.00	0.24	0.00	0.24
D(Max) = Max. Depth (m):	0.00	0.09	0.00	0.09
D(Ave) = Ave. Depth (m):	0.00	0.04	0.00	0.04
V = Ave. Velocity (m/s):	0.00	1.72	0.00	1.72
D(Max) x V (cumecs/m):	0.00	0.15	0.00	0.15
D(Ave) x V (cumecs/m):	0.00	0.06	0.00	0.06
Froude Number:	0.00	2.92	0.00	N/A
Area (m ²):	0.00	0.14	0.00	0.14
Wetted Perimeter (m):	0.00	4.11	0.00	4.11
Flow Width (m):	0.00	3.97	0.00	3.97
Hydraulic Radius (m):	0.00	0.03	0.00	0.03
Composite Manning's n:	0.000	0.013	0.000	N/A
Split Flow?	-	-	-	Yes

4. CROSS-SECTION DATA:

SEGMENT NO.	LEFT HAND POINT CHAINAGE (m)	R.L. (m)	RIGHT HAND POINT CHAINAGE (m)	R.L. (m)	MANNING'S N
1	-8.000	45.974	-7.950	45.973	0.035
2	-7.950	45.973	-6.450	45.943	0.013
3	-6.450	45.943	-3.800	45.731	0.035
4	-3.800	45.731	-3.690	45.731	0.013
5	-3.690	45.731	-3.650	45.581	0.013
6	-3.650	45.581	-3.200	45.621	0.013
7	-3.200	45.621	0.000	45.727	0.013
8	0.000	45.727	3.200	45.621	0.013
9	3.200	45.621	3.650	45.581	0.013
10	3.650	45.581	3.690	45.731	0.013
11	3.690	45.731	3.800	45.731	0.013
12	3.800	45.731	6.450	45.819	0.035
13	6.450	45.819	7.950	45.849	0.013
14	7.950	45.849	8.000	45.851	0.035



2. DISCHARGE INFORMATION:

100 year (1%) storm event

Total discharge = 0.062 cumecs

There is no pipe discharge
Overland / Channel / Watercourse discharge = 0.062 cumecs


3. RESULTS: Water surface elevation = 48.491m

High Flow Channel grade = 1 in 200, Main Channel / Low Flow Channel grade = 1 in 200.

	LEFT OVERBANK	MAIN CHANNEL	RIGHT OVERBANK	TOTAL CROSS-SECTION
Discharge (cumecs):	0.00	0.08	0.00	0.08
D(Max) = Max. Depth (m):	0.00	0.09	0.00	0.09
D(Ave) = Ave. Depth (m):	0.00	0.04	0.00	0.04
V = Ave. Velocity (m/s):	0.00	0.57	0.00	0.57
D(Max) x V (cumecs/m):	0.00	0.05	0.00	0.05
D(Ave) x V (cumecs/m):	0.00	0.02	0.00	0.02
Froude Number:	0.00	0.97	0.00	N/A
Area (m ²):	0.00	0.14	0.00	0.14
Wetted Perimeter (m):	0.00	4.11	0.00	4.11
Flow Width (m):	0.00	3.97	0.00	3.97
Hydraulic Radius (m):	0.00	0.03	0.00	0.03
Composite Manning's n:	0.000	0.013	0.000	N/A
Split Flow?	-	-	-	Yes

4. CROSS-SECTION DATA:

SEGMENT NO.	LEFT HAND POINT CHAINAGE (m)	R.L. (m)	RIGHT HAND POINT CHAINAGE (m)	R.L. (m)	MANNING'S N
1	-8.000	48.671	-7.950	48.669	0.035
2	-7.950	48.669	-6.450	48.639	0.013
3	-6.450	48.639	-3.800	48.551	0.035
4	-3.800	48.551	-3.690	48.551	0.013
5	-3.690	48.551	-3.650	48.401	0.013
6	-3.650	48.401	-3.200	48.441	0.013
7	-3.200	48.441	0.000	48.547	0.013
8	0.000	48.547	3.200	48.441	0.013
9	3.200	48.441	3.650	48.401	0.013
10	3.650	48.401	3.690	48.551	0.013
11	3.690	48.551	3.800	48.551	0.013
12	3.800	48.551	6.450	48.639	0.035
13	6.450	48.639	7.950	48.669	0.013
14	7.950	48.669	8.000	48.671	0.035



2. DISCHARGE INFORMATION:

100 year (1%) storm event

Total discharge = 0.317 cumecs

There is no pipe discharge
Overland / Channel / Watercourse discharge = 0.317 cumecs


3. RESULTS: Water surface elevation = 45.098m

High Flow Channel grade = 1 in 50, Main Channel / Low Flow Channel grade = 1 in 50.

	LEFT OVERBANK	MAIN CHANNEL	RIGHT OVERBANK	TOTAL CROSS-SECTION
Discharge (cumecs):	0.00	0.41	0.00	0.41
D(Max) = Max. Depth (m):	0.00	0.12	0.00	0.12
D(Ave) = Ave. Depth (m):	0.00	0.05	0.00	0.05
V = Ave. Velocity (m/s):	0.00	1.44	0.00	1.44
D(Max) x V (cumecs/m):	0.00	0.17	0.00	0.17
D(Ave) x V (cumecs/m):	0.00	0.07	0.00	0.07
Froude Number:	0.00	2.06	0.00	N/A
Area (m ²):	0.00	0.29	0.00	0.29
Wetted Perimeter (m):	0.00	5.94	0.00	5.94
Flow Width (m):	0.00	5.75	0.00	5.75
Hydraulic Radius (m):	0.00	0.05	0.00	0.05
Composite Manning's n:	0.000	0.013	0.000	N/A
Split Flow?	-	-	-	Yes

4. CROSS-SECTION DATA:

SEGMENT NO.	LEFT HAND POINT CHAINAGE (m)	R.L. (m)	RIGHT HAND POINT CHAINAGE (m)	R.L. (m)	MANNING'S N
1	-8.491	45.330	-8.000	45.248	0.013
2	-8.000	45.248	-7.950	45.247	0.035
3	-7.950	45.247	-6.450	45.217	0.013
4	-6.450	45.217	-3.800	45.128	0.035
5	-3.800	45.128	-3.690	45.128	0.013
6	-3.690	45.128	-3.650	44.978	0.013
7	-3.650	44.978	-3.200	45.018	0.013
8	-3.200	45.018	0.000	45.128	0.013
9	0.000	45.128	3.200	45.018	0.013
10	3.200	45.018	3.650	44.978	0.013
11	3.650	44.978	3.690	45.128	0.013
12	3.690	45.128	3.800	45.128	0.013
13	3.800	45.128	6.450	45.217	0.035
14	6.450	45.217	7.950	45.247	0.013



2. DISCHARGE INFORMATION:

100 year (1%) storm event

Total discharge = 0.132 cumecs

There is no pipe discharge
Overland / Channel / Watercourse discharge = 0.132 cumecs


3. RESULTS: Water surface elevation = 47.888m

High Flow Channel grade = 1 in 37.6598, Main Channel / Low Flow Channel grade = 1 in 37.6598.

	LEFT OVERBANK	MAIN CHANNEL	RIGHT OVERBANK	TOTAL CROSS-SECTION
Discharge (cumecs):	0.00	0.13	0.00	0.13
D(Max) = Max. Depth (m):	0.00	0.08	0.00	0.08
D(Ave) = Ave. Depth (m):	0.00	0.03	0.00	0.03
V = Ave. Velocity (m/s):	0.00	1.21	0.00	1.21
D(Max) x V (cumecs/m):	0.00	0.10	0.00	0.10
D(Ave) x V (cumecs/m):	0.00	0.04	0.00	0.04
Froude Number:	0.00	2.19	0.00	N/A
Area (m ²):	0.00	0.10	0.00	0.10
Wetted Perimeter (m):	0.00	3.46	0.00	3.46
Flow Width (m):	0.00	3.34	0.00	3.34
Hydraulic Radius (m):	0.00	0.03	0.00	0.03
Composite Manning's n:	0.000	0.013	0.000	N/A
Split Flow?	-	-	-	Yes

4. CROSS-SECTION DATA:

SEGMENT NO.	LEFT HAND POINT CHAINAGE (m)	R.L. (m)	RIGHT HAND POINT CHAINAGE (m)	R.L. (m)	MANNING'S N
1	-8.000	48.078	-7.950	48.077	0.035
2	-7.950	48.077	-6.450	48.047	0.013
3	-6.450	48.047	-3.800	47.958	0.035
4	-3.800	47.958	-3.690	47.958	0.013
5	-3.690	47.958	-3.650	47.808	0.013
6	-3.650	47.808	-3.200	47.848	0.013
7	-3.200	47.848	0.000	47.955	0.013
8	0.000	47.955	3.200	47.848	0.013
9	3.200	47.848	3.650	47.808	0.013
10	3.650	47.808	3.690	47.958	0.013
11	3.690	47.958	3.800	47.958	0.013
12	3.800	47.958	6.450	48.047	0.035
13	6.450	48.047	7.950	48.077	0.013
14	7.950	48.077	8.000	48.078	0.035



2. DISCHARGE INFORMATION:

100 year (1%) storm event


Total discharge = 1.31 cumecs

There is no pipe discharge
Overland / Channel / Watercourse discharge = 1.314 cumecs

3. RESULTS: Water surface elevation = 44.220m


High Flow Channel grade = 1 in 200, Main Channel / Low Flow Channel grade = 1 in 200.

	LEFT OVERBANK	MAIN CHANNEL	RIGHT OVERBANK	TOTAL CROSS-SECTION
Discharge (cumecs):	0.00	0.17	0.00	0.17
D(Max) = Max. Depth (m):	0.00	0.14	0.00	0.14
D(Ave) = Ave. Depth (m):	0.00	0.06	0.00	0.06
V = Ave. Velocity (m/s):	0.00	0.81	0.00	0.81
D(Max) x V (cumecs/m):	0.00	0.11	0.00	0.11
D(Ave) x V (cumecs/m):	0.00	0.05	0.00	0.05
Froude Number:	0.00	1.06	0.00	1.06
Area (m ²):	0.00	0.21	0.00	0.21
Wetted Perimeter (m):	0.00	3.62	0.00	3.62
Flow Width (m):	0.00	3.51	0.00	3.51
Hydraulic Radius (m):	0.00	0.06	0.00	0.06
Composite Manning's n:	0.000	0.013	0.000	0.013
Split Flow?	-	-	-	No



file name 309442CD505.dwg, layout name CD505, plotted by Thash Nguyen, file location G:\30\309442 CIVIL\A\A0 plot date 18/03/2025 10:58 AM Sheet 1 of 1 Sheets

D	CATCHMENTS AMENDED	G.K	18/03/25
C	CATCHMENTS AMENDED	G.K	28/01/25
B	CATCHMENTS AMENDED	G.K	18/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24
Rev	Amendments	Approved	Date



System Certified

© Spiire Australia Pty Ltd All Rights Reserved

This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635



Designed
T. NGUYEN

Authorised
G. KOHLMAN


Checked
G. KOHLMAN

Date
01/11/24


HARLOW ESTATE
STAGE 6
DRAINAGE COMPUTATIONS
5YR CATCHMENT PLAN - SHEET 1
WYNDHAM CITY COUNCIL
SIG GROUP

PRELIMINARY Drg No 309442CD505 Rev

D



Rev	Amendments	Approved	Date
A	ISSUED TO COUNCIL	G.K	01/11/24
B	CATCHMENTS AMENDED	G.K	18/12/24
C	CATCHMENTS AMENDED	G.K	28/01/25
D	CATCHMENTS AMENDED	G.K	18/03/25



© Spiire Australia Pty Ltd All Rights Reserved
This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 3007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635




Designed
T. NGUYEN
Authorised
G. KOHLMAN

Checked
G. KOHLMAN
Date
01/11/24

HARLOW ESTATE
STAGE 6
DRAINAGE COMPUTATIONS
5YR CATCHMENT PLAN - SHEET 2
WYNDHAM CITY COUNCIL
SIG GROUP

PRELIMINARY Drg No 309442CD506 Rev D

file name 309442CD506.dwg, layout name CD506, plotted by Thach Nguyen, file location G:\309442 CD506\A1.dwg, plot date 18/03/2025 10:58 AM, sheet 1 of 1 sheets



A	ISSUED TO COUNCIL	G.K	01/11/24
Rev	Amendments	Approved	Date



Scale
H 1:500
SCALE @ A1

© Spiire Australia Pty Ltd All Rights Reserved
This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

spiire
L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635


Harlow
T A R N E I T
Designed
T. NGUYEN
Authorised
G. KOHLMAN
Checked
G. KOHLMAN
Date
01/11/24

HARLOW ESTATE
STAGE 6
DRAINAGE COMPUTATIONS
5YR CATCHMENT PLAN - SHEET 3
WYNDHAM CITY COUNCIL
SIG GROUP
PRELIMINARY
Drg No
309442CD507
Rev
A



file name 309442CD508.dwg, layout name CD508, plotted by Thanh Nguyen,
file location G:\309442\CD508\A1.dwg, plot date 18/03/2025 10:58 AM, Sheet 1 of 1 Sheets

Rev	Amendments	Approved	Date
B	CATCHMENTS AMENDED	G.K	18/12/24
A	ISSUED TO COUNCIL	G.K	01/11/24



© Spiire Australia Pty Ltd All Rights Reserved
This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

spiire
L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635

Harlow
TARNEIT
Designed
T. NGUYEN
Authorised
G. KOHLMAN
Checked
G. KOHLMAN
Date
01/11/24

HARLOW ESTATE
STAGE 6
DRAINAGE COMPUTATIONS
5YR CATCHMENT PLAN - SHEET 4
WYNDHAM CITY COUNCIL
SIG GROUP
PRELIMINARY Drg No **309442CD508** Rev **B**

file name: 309442CD509.dwg, layout name: CD509, plotted by: Thach Nguyen, file location: G:\30309442\CD509\plot.dwg, date: 18/03/2025 10:58 AM, sheet: 1 of 1, sheets:

			SUB-CATCHMENT RUNOFF						DRAIN DESIGN										HEADLOSSES										PART FULL		DESIGN LEVELS							
STRUCTURE No.	DOWNSTREAM STRUCTURE No.	PIT TYPE	C CO-EFFICIENT OF RUNOFF	A SUB-CATCHMENT AREA (ROAD)	C CO-EFFICIENT OF RUNOFF	A SUB-CATCHMENT AREA (LOT)	C CO-EFFICIENT OF RUNOFF	A SUB-CATCHMENT AREA (MISC)	Q SUB-CATCHMENT DISCHARGE	t _c CRITICAL TIME OF CONCENTRATION	i RAINFALL INTENSITY	A CUMULATIVE CATCHMENT AREA	C EFFECTIVE CO-EFFICIENT OF RUNOFF	CA TOTAL (C x A)	Q _p PIPE FLOW	L REACH LENGTH	S PIPE GRADE	T PIPE DIAMETER	Q _{cap} PIPE GRADE CAPACITY	Q _a /Q _{cap} Q(actual) / Q(capacity)	V _{cap} CAPACITY VELOCITY (Q _{cap} /AREA)	TIME IN PIPE	V _{2/2g} PIPE VELOCITY HEAD	K _u US PIT HEADLOSS COEFF	h _u US PIT PRESSURE HEADLOSS	K _w W.S.E. COEFF	h _w CHANGE IN W.S.E	S _f PIPE FRICTION SLOPE	h _f PIPE FRICTION (HEADLOSS L'S)	NORMAL DEPTH	NORMAL DEPTH VELOCITY	UPSTREAM PIPE H.G.L	DOWNSTREAM PIPE H.G.L	PIT GRATE LEVEL	CALCULATED FREEBOARD	STRUCTURE		
				ha		ha		ha	l/s	min	mm/hr	ha		ha	l/s	m	(1 in)	mm	l/s	%	m/s	min.	m			m		m	%	m	m	m	m/s	m	m	m	m	
148TP	1	TANGENT POINT								12.05	59.529	18.169	0.638	11.593	1937	4.57	500	1350	2388	80	1.668	0.046	0.092	0.00	0.000		0.000	0.129	0.006	0.916	1.85	46.499	46.493	47.741	1.242			
1TP	148TP	TANGENT POINT								12.03	59.592	18.169	0.638	11.593	1937	2.61	500	1350	2388	80	1.668	0.026	0.092	0.00	0.000		0.000	0.129	0.003	0.917	1.85	46.502	46.499	47.693	1.190			
2TP	1TP	TANGENT POINT								11.86	60.006	18.169	0.638	11.593	1937	17.09	500	1350	2388	81	1.668	0.171	0.093	0.00	0.000		0.000	0.131	0.022	0.921	1.86	46.525	46.502	47.476	0.953			
3	2TP	JUNCTION PIT							0	11.80	60.152	18.169	0.638	11.593	1937	6.07	500	1350	2388	81	1.668	0.061	0.093	0.50	0.047		0.047	0.132	0.008	0.923	1.86	46.533	46.525	47.564	0.985			
4TP	3	TANGENT POINT								11.40	61.116	17.090	0.637	10.890	1868	39.87	500	1350	2388	77	1.668	0.398	0.085	0.00	0.000		0.000	0.120	0.048	0.892	1.84	46.627	46.579	47.739	1.112			
5TP	4TP	TANGENT POINT								11.29	61.372	17.090	0.637	10.890	1868	10.57	500	1350	2388	78	1.668	0.106	0.086	0.00	0.000		0.000	0.121	0.013	0.895	1.84	46.640	46.627	47.756	1.116			
6	5TP	JUNCTION PIT	0.561	0.063					8	11.14	61.753	17.090	0.637	10.890	1868	15.76	500	1350	2388	78	1.668	0.157	0.087	0.50	0.043		0.043	0.122	0.019	0.899	1.85	46.659	46.640	47.523	0.820			
7	6	JUNCTION PIT	0.561	0.056					8	10.39	63.566	16.493	0.636	10.497	1853	75.00	500	1350	2388	78	1.668	0.749	0.086	0.50	0.043		0.043	0.120	0.090	0.894	1.84	46.793	46.703	47.646	0.812			
8	7	JUNCTION PIT							0	10.20	64.008	16.437	0.637	10.466	1861	18.28	500	1350	2388	78	1.668	0.183	0.086	0.50	0.043		0.043	0.121	0.022	0.896	1.84	46.858	46.836	47.926	1.025			
9	8	JUNCTION PIT							0	9.51	66.620	15.514	0.637	9.875	1827	26.95	500	1350	2388	77	1.668	0.269	0.083	0.70	0.058		0.058	0.117	0.032	0.885	1.84	46.933	46.901	48.045	1.058			
10TP	9	TANGENT POINT								9.88	64.999	12.211	0.626	7.644	1399	4.65	500	1200	1744	79	1.542	0.050	0.076	0.00	0.000		0.000	0.125	0.006	0.806	1.71	46.997	46.991	47.975	0.978			
11	10TP	JUNCTION PIT	0.561	0.039	0.708	0.021			9	9.68	65.876	12.211	0.626	7.644	1399	18.86	500	1200	1744	80	1.542	0.204	0.078	0.50	0.039		0.039	0.129	0.024	0.814	1.71	47.021	46.997	48.093	1.033			
12	11	JUNCTION PIT			0.708	0.074			13	9.18	68.006	12.128	0.626	7.594	1435	45.85	500	1200	1744	82	1.542	0.495	0.082	0.50	0.041		0.041	0.135	0.062	0.829	1.72	47.122	47.060	48.043	0.880			
12ATP	12	TANGENT POINT								9.02	68.720	10.254	0.620	6.359	1215	15.73	400	1050	1366	89	1.577	0.166	0.100	0.00	0.000		0.000	0.197	0.031	0.771	1.78	47.194	47.163	47.914	0.720			
13	12ATP	JUNCTION PIT	0.561	0.082					11	9.00	68.779	10.254	0.620	6.359	1215	1.28	400	1050	1366	89	1.578	0.014	0.100	1.50	0.151		0.151	0.198	0.003	0.771	1.78	47.197	47.194	47.708	0.361			
14	13	JUNCTION PIT	0.561	0.074	0.708	0.102			27	12.65	58.096	6.121	0.585	3.579	578	30.47	263	1050	1683	34	1.944	0.261	0.023	0.50	0.011		0.011	0.045	0.014	0.424	1.76	47.361	47.347	47.810	0.437			
15	14	JUNCTION PIT	0.561	0.084	0.708	0.219			48	11.90	59.907	5.945	0.583	3.465	577	73.83	300	900	1046	55	1.644	0.749	0.042	0.50	0.021		0.021	0.101	0.075	0.477	1.68	47.447	47.372	48.056	0.588			
16	15	JUNCTION PIT							0	11.19	61.617	5.536	0.579	3.204	548	83.72	185	825	1056	52	1.975	0.706	0.054	0.50	0.027		0.027	0.146	0.122	0.422	1.99	47.590	47.468	48.608	0.991			
17	16	JUNCTION PIT	0.561	0.051	0.708	0.294			57	11.10	61.845	5.518	0.579	3.194	549	9.03	250	750	704	78	1.594	0.094	0.079	0.50	0.039		0.039	0.243	0.022	0.498	1.76	47.639	47.617	48.365	0.687			
18	17	GRADED SIDE ENTRY PIT	0.561	0.046	0.708	0.174			36	10.57	63.130	5.122	0.572	2.928	513	50.92	249	750	706	73	1.598	0.531	0.069	0.50	0.034		0.034	0.213	0.108	0.475	1.74	47.786	47.678	48.535	0.714			
EX1	18	JUNCTION PIT			0.708	0.102			17	10.33	63.710	4.856	0.567	2.754	487	33.19	104	675	826	59	2.308	0.240	0.095	0.50	0.047		0.047	0.336	0.111	0.373	2.40	47.932	47.821	48.820	0.841			
19	EX1	JUNCTION PIT							0	10.25	63.894	4.754	0.564	2.681	476	7.31	213	675	576	83	1.611	0.076	0.090	0.50	0.045		0.045	0.320	0.023	0.468	1.80	48.003	47.980	48.845	0.796			
EX2	19	JUNCTION PIT	0.561	4.659					466	10.15	64.137	4.659	0.561	2.614	466	9.72	213	675	576	81	1.611	0.101	0.086	0.43	0.037		0.037	0.307	0.030	0.460	1.79	48.078	48.048	48.874	0.759			
20	9	JUNCTION PIT							0	8.80	69.655	3.641	0.667	2.428	470	12.55	63	675	1063	44	2.970	0.070	0.088	0.90	0													

file name: 309442CD510.dwg, layout name: CD510, plotted by: Thanh Nguyen, file location: G:\30\309442\CD510\ACAD plot date: 18/03/2025 10:58 AM, Sheet: 1 of 1, Sheets:

STRUCTURE No.	DOWNSTREAM STRUCTURE No.	PIT TYPE	SUB-CATCHMENT RUNOFF						DRAIN DESIGN										HEADLOSSES										PART FULL		DESIGN LEVELS				STRUCTURE	
			CO-EFFICIENT OF RUNOFF	SUB-CATCHMENT AREA (ROAD)	CO-EFFICIENT OF RUNOFF	SUB-CATCHMENT AREA (LOT)	CO-EFFICIENT OF RUNOFF	SUB-CATCHMENT AREA (MISC)	SUB-CATCHMENT DISCHARGE	CRITICAL TIME OF CONCENTRATION	RAINFALL INTENSITY	CUMULATIVE CATCHMENT AREA	EFFECTIVE CO-EFFICIENT OF RUNOFF	TOTAL (C x A)	PIPE FLOW	REACH LENGTH	PIPE GRADE	PIPE DIAMETER	PIPE GRADE CAPACITY	Qa/Qcap	Vcap	TIME IN PIPE	PIPE VELOCITY HEAD	U/S PIT HEADLOSS COEFF	U/S PIT PRESSURE HEADLOSS	W.S.E. COEFF	CHANGE IN W.S.E.	PIPE FRICTION SLOPE	PIPE FRICTION (HEADLOSS L'S)	NORMAL DEPTH	NORMAL DEPTH VELOCITY	UPSTREAM PIPE H.G.L	DOWNSTREAM PIPE H.G.L	PIT GRATE LEVEL		CALCULATED FREEBOARD
ha	ha	l/s	min	mm/hr	ha	ha	ha	l/s	m	(1 in)	mm	l/s	%	m/s	min	m	m	m	m	m	m	m	m	m	m	m	m	m	m	m	m	m	m	m	m	
81EP	80	ENDPIPE			0.635	4.103			529	8.00	73.100	4.103	0.635	2.606	529	5.10	400	900	906	58	1.423	0.080	0.035	0.00	0.000		0.000	0.085	0.004	0.494	1.48	47.683	47.679	48.476	0.793	
82	79	GRATED SIDE ENTRY PIT	0.561	0.051					7	6.38	80.076	0.459	0.649	0.298	66	2.92	200	300	68	97	0.968	0.050	0.045	0.50	0.022		0.022	0.469	0.014	0.238	1.10	47.661	47.647	48.154	0.471	
83EP	82	ENDPIPE							0	6.12	81.196	0.408	0.660	0.269	62	19.12	125	300	87	70	1.224	0.260	0.038	0.00	0.000		0.000	0.394	0.075	0.185	1.32	47.758	47.683	48.436	0.678	
84	83EP	GRATED SIDE ENTRY PIT	0.561	0.067	0.708	0.109			27	5.68	83.066	0.408	0.660	0.269	62	31.95	125	300	87	72	1.224	0.435	0.039	2.20	0.087		0.087	0.412	0.132	0.188	1.33	47.890	47.758	48.460	0.483	
85	48	GRATED SIDE ENTRY PIT	0.561	0.046					6	5.00	86.000	0.046	0.561	0.026	6	6.70	95	300	99	6	1.401	0.080	0.000	5.00	0.002		0.002	0.004	0.000	0.051	0.78	48.058	48.058	48.702	0.642	
86	47	GRATED SIDE ENTRY PIT	0.561	0.046					6	5.00	86.000	0.046	0.561	0.026	6	6.70	100	300	97	6	1.369	0.082	0.000	5.00	0.002		0.002	0.004	0.000	0.051	0.77	47.718	47.718	48.300	0.580	
87	17	GRATED SIDE ENTRY PIT	0.561	0.051					7	5.00	86.000	0.051	0.561	0.029	7	11.80	41	300	151	5	2.137	0.092	0.000	5.00	0.002		0.002	0.005	0.001	0.043	1.08	47.679	47.678	48.366	0.684	
88	16	GRATED SIDE ENTRY PIT	0.561	0.009					1	5.06	85.733	0.018	0.561	0.010	2	2.30	50	300	137	2	1.936	0.020	0.000	0.50	0.000		0.000	0.001	0.000	0.028	0.74	47.617	47.617	48.411	0.794	
89	88	GRATED SIDE ENTRY PIT	0.561	0.009					1	5.00	86.000	0.009	0.561	0.005	1	7.20	50	300	137	1	1.936	0.062	0.000	5.00	0.000		0.000	0.000	0.000	0.020	0.60	47.617	47.617	48.411	0.794	
90	15	GRATED SIDE ENTRY PIT	0.561	0.105					14	5.00	86.000	0.105	0.561	0.059	14	11.80	27	300	187	8	2.650	0.074	0.002	5.00	0.010		0.010	0.021	0.003	0.056	1.56	47.471	47.468	48.056	0.575	
91	11	GRATED SIDE ENTRY PIT	0.561	0.023					3	5.00	86.000	0.023	0.561	0.013	3	8.50	50	300	137	2	1.936	0.073	0.000	5.00	0.000		0.000	0.001	0.000	0.031	0.79	47.060	47.060	48.093	1.032	
92EP	63	ENDPIPE							0	5.12	85.503	0.054	0.650	0.035	8	6.08	17	300	235	4	3.319	0.031	0.001	0.00	0.000		0.000	0.007	0.000	0.039	1.56	47.202	47.202	48.178	0.976	
93	92EP	JUNCTION PIT	0.561	0.021					3	5.11	85.539	0.054	0.650	0.035	8	1.64	17	300	235	4	3.319	0.008	0.001	1.39	0.001		0.001	0.007	0.000	0.039	1.56	47.202	47.202	48.078	0.875	
94	73	GRATED SIDE ENTRY PIT	0.561	0.027	0.708	0.121			24	5.95	81.920	0.407	0.645	0.262	60	69.24	180	300	72	83	1.020	1.131	0.036	1.70	0.062		0.062	0.381	0.264	0.208	1.14	48.074	47.810	48.614	0.478	
95	94	GRATED SIDE ENTRY PIT	0.561	0.038	0.708	0.035			11	5.77	82.709	0.258	0.624	0.161	37	11.53	230	375	116	32	1.047	0.183	0.006	1.90	0.011		0.011	0.045	0.005	0.146	0.93	48.141	48.136	48.522	0.370	
96	95	GRATED SIDE ENTRY PIT	0.561	0.016	0.708	0.075			15	5.00	86.000	0.114	0.658	0.075	18	46.85	180	300	72	25	1.020	0.765	0.003	0.90	0.003		0.003	0.034	0.016	0.102	0.85	48.168	48.152	48.756	0.585	
97	96	JUNCTION PIT							0	5.23	85.001	0.024	0.561	0.013	3	8.27	180	300	72	4	1.020	0.135	0.000	0.20	0.000		0.000	0.001	0.000	0.043	0.51	48.171	48.171	49.094	0.923	
98	97	GRATED SIDE ENTRY PIT	0.561	0.012					2	5.14	85.382	0.024	0.561	0.013	3	5.43	180	300	72	4	1.020	0.089	0.000	1.50	0.000		0.000	0.001	0.000	0.043	0.51	48.171	48.171	48.820	0.649	
99	98	GRATED SIDE ENTRY PIT	0.561	0.012					2	5.00	86.000	0.012	0.561	0.007	2	11.80	100	300	97	2	1.369	0.144	0.000	5.00	0.000		0.000	0.000	0.000	0.027	0.51	48.171	48.171	48.820	0.649	
100	84	JUNCTION PIT			0.708	0.165			28	5.00	86.000	0.165	0.708	0.117	28	58.50	92	300	101	28	1.429	0.682	0.008	5.00	0.040		0.040	0.084	0.049	0.108	1.22	48.026	47.977	48.978	0.914	
101	73	GRATED SIDE ENTRY PIT	0.561	0.042					6	5.00	86.000	0.042	0.561	0.024	6	8.50	180	300	72	8	1.020	0.139	0.000	5.00	0.002		0.002	0.003	0.000	0.057	0.61	47.811	47.810	48.350	0.538	
102	95	GRATED SIDE ENTRY PIT	0.561	0.072					10	5.00	86.000	0.072	0.561	0.040	10	8.50	28	300	183	5	2.594	0.055	0.001	5.00	0.005		0.005	0.010	0.001	0.047	1.37	48.153	48.152	48.522	0.364	
103	84	GRATED SIDE ENTRY PIT	0.561	0.067					9	5.00	86.000	0.067	0.561	0.037	9	11.80	95	300	99	9	1.401	0.140	0.001	5.00	0.004		0.004	0.009	0.001	0.061	0.87	47.978	47.977	48.460	0.478	
104	61	GRATED SIDE ENTRY PIT			0.708	0.138			23	5.76	82.727	0.406	0.656	0.266	61	65.74	230	375	116	53	1.047	1.046	0.016	1.70	0.027		0.027	0.122	0.080	0.194	1.06	47.610	47.530	48.236	0.599	
105	104	GRATED SIDE ENTRY PIT	0.561	0.052	0.708	0.031			12	5.58	83.516	0.288	0.630	0.169	39	11.53	230	375	116	34	1.047	0.183	0.006	1.90	0.012		0.012	0.050	0.006	0.150	0.95	47.642	47.637	48.142	0.487	
106	105	GRATED SIDE ENTRY PIT	0.561	0.030	0.708	0.094			20	5.00	86.000	0.124	0.673	0.083	20	47.80	99	300	97	20	1.379	0.578	0.004	5.00	0.020		0.020	0.042	0.020	0.092	1.08	47.675	47.655	48.381	0.686	
107	58	GRATED SIDE ENTRY PIT	0.561	0.055	0.708	0.149			33	5.00	86.000	0.204	0.668	0.136	33	51.20	300	600	355	9	1.254	0.680	0.001	5.00	0.003		0.003	0.003	0.001	0.123	0.78	47.247	47.246	47.602	0.351	
108	67	JUNCTION PIT			0.708	0.258			44	5.00	86.000	0.258	0.708	0.182	44	76.50	167	300	75	58	1.060	1.203	0.019	5.00	0.097		0.097	0.203	0.155	0.164	1.10	47.567	47.412	48.058	0.392	
109	61	GRATED SIDE ENTRY PIT	0.561	0.053					7	5.00	86.000	0.053	0.561	0.030	7	8.50	14	300	259	3	3.669	0.039	0.001	5.00	0.003		0.003	0.005	0.000	0.034	1.59	47.530	47.530	48.232	0.699	